

**INVITATION FOR TENDER FOR INTERIOR DECORATION FOR PROPOSED
JHENAIDAH BRANCH**

Sealed tender is hereby invited from the eligible Tenderers who can participate in tender as defined in the tender documents of the under mentioned works as per terms & conditions stated below:

1. Procuring Entity : Modhumoti Bank PLC., Common Services Division, Khandker Tower (Level-7), 94 Gulshan Avenue, Gulshan-1, Dhaka-1212
2. Tender Name : **Civil and interior/ exterior for JHENAIDAH BRANCH, Khulna (Proposed) as well as ATM booth at the same location.**
3. Time of completion of work : The Branch @ 35 days from the date of issuance Work Order.
4. Eligibility of Tenderers
 - i) The Tenderer shall be given priority who has experience of "Construction, Interior decoration and Furniture supply works" in the field of Bank Interiors in Bangladesh, which must be executed by the contractor during last three financial years.
 - ii) All experiences must be backed by with proper documentation (i.e. work order, completion certificate) from respective banks.
 - iii) Up to date Trade license, Income Tax clearance certificate, VAT & BIN Certificate.
 - iv) Must be financially solvent.
5. Price of Tender Document : Will be distributed through mail. No Purchase value.
6. Amount of Tender Security : No Tender Security Money.
7. Name & address of the office from where tender documents to be obtained & dropped : Modhumoti Bank PLC., Common Services Division, Khandker Tower (Level-7), 94 Gulshan Avenue, Gulshan-1, Dhaka-1212.
8. Last date & time for tender submission : **On or before 2.30 P.M. on 07.10.2025.**
9. Pre-Bid Meeting : **On 04.10.2025 at 3.00 P.M.**
10. Date & time for tender opening : **At Bank's own discretion through Bank's internal committee**
11. Special instructions : Modhumoti Bank PLC. reserves the right to accept partly or fully any tender or reject any tender and not bound to accept the lowest quotation, without assigning any reason whatsoever.


(S.M Shahin Iqbal)
Vice President
Head of Common Services Division



MODHUMOTI BANK PLC.

COMMON SERVICES DIVISION, HEAD OFFICE
CSD, Khandker Tower (Level-7 & 8), 94 Gulshan Avenue, Gulshan-1,
Dhaka-1212

TENDER FOR INTERIOR DECORATION
AND RELATED WORKS For Opening JHENAIDAH Branch,
JHENAIDAH as well as ATM Booth at the said location

SEPTEMBER-2025

MODHUMOTI BANK PLC.
COMMON SERVICES DIVISION
CSD, Khandker Tower (Level-7 & 8),
94 Gulshan Avenue,
Gulshan-1, Dhaka-1212



MODHUMOTI BANK PLC.

COMMON SERVICES DIVISION, HEAD OFFICE
CSD, Khandker Tower (Level-7 & 8), 94 Gulshan Avenue, Gulshan-1,
Dhaka-1212

PACKAGE – 1

PART I

PAPERS AND DOCUMENTS

PART II

**SPECIFICATIONS, SCHEDULE OF ITEMS AND BILL OF
QUANTITY**




MODHUMOTI BANK PLC.

COMMON SERVICES DIVISION, HEAD OFFICE
CSD, Khandker Tower (Level-7 & 8), 94 Gulshan Avenue, Gulshan-1,
Dhaka-1212

PART 1

PAPERS AND DOCUMENTS

1. TENDER NOTICE
2. ABSTRACT OF THE TENDER



MODHUMOTI BANK PLC.

COMMON SERVICES DIVISION, HEAD OFFICE
CSD, Khandker Tower (Level-7 & 8), 94 Gulshan Avenue, Gulshan-1,
Dhaka-1212

TENDER NOTICE

SECTION 1



MODHUMOTI BANK PLC., Khandker Tower (Level-7 & 8), 94 Gulshan Avenue, Gulshan-1, Dhaka-1212

TENDER NOTICE

1.01 TENDER NOTICE

Tender is sealed covers in prescribed form are hereby invited by the undersigned from reputed firms engaged in constructions, Interior Decoration having experience in the field of Bank/Insurance/ Reputed office interiors in Bangladesh.

1.02 NAME OF WORK

Interior decoration & other related works for opening of Bank's Jhenaidah Branch, Jhenaidah as well as ATM booth at the said location.

1.03 SALE OF TENDER DOCUMENTS

Tender documents will be mailed to their authorized (as submitted to the Bank) for submission of the same as per rules. No purchase is required in this regard.

1.04 OPENING OF TENDER DOCUMENT

Tender will be received by the office of the undersigned within 2.30 P.M. on October 07, 2025.

1.05 SECURITY DEPOSIT

The Bank would retain a total of 10% of the certified bill amount as security deposit from the awarded vendor.

1.06 TIME FOR COMPLETION

Time for completion of works is 30 (thirty) days from the date of issue of the written work order.

1.07 SITE VISIT

The bidder must visit the respective site of work and make him fully acquainted with the site condition & see Scope of works and the available space, services and conceptual design drawings before submitting tender.

1.08 SUBMITTANCE

The undersigned has the right to accept or reject any or all the offers without assigning any reason whatsoever. The Undersigned also reserves the right to split up the work between two or more Contractors.

1.09 EARNEST MONEY

Not Required.

VICE PRESIDENT & HEAD OF DIVISION
COMMON SERVICES DIVISION
CSD, Khandker Tower (Level-7 & 8),
94 Gulshan Avenue,
Gulshan-1, Dhaka-1212



MODHUMOTI BANK PLC.
COMMON SERVICES DIVISION, HEAD OFFICE
CSD, Khandker Tower (Level-7 & 8), 94 Gulshan Avenue, Gulshan-1,
Dhaka-1212

ABSTRACT OF THE TENDER

SECTION 2



MODHUMOTI BANK PLC., Khandker Tower (Level-7 & 8), 94 Gulshan Avenue, Gulshan-1, Dhaka-1212.

ABSTRACT OF TENDER

2.01	NAME OF THE OWNER	MODHUMOTI BANK PLC.
2.02	NAME OF THE PROJECT	INTERIOR DECORATION AND RELATED WORKS OPENING OF JHENAIDAH BRANCH, JHENAIDAH AS WELL AS ATM BOOTH
2.03	PROJECT SITE	JHENAIDAH BRANCH, JHENAIDAH
2.04	SECURITY DEPOSIT	10% of the certified final bill amount and fully refunded after Twelve months from the date of hand over of the project.
2.05	VALIDITY OF TENDER	30 (Thirty) days.
2.06	DATE OF AWARD OF WORK	The date of issue of order in writing [work order] to Commence the work.
2.07	TIME OF COMPLETION	30 [Thirty] days from the date of issuing written work Order.
2.08	PERIOD OF MAINTENANCE	12 [Twelve] months from the date of issue of final certificate of completion by the authority.
2.09	PAYMENT	All payments shall be in Taka on submission of bill and Consequent certification by the Authority after opening of the project. All local taxes, duties, Govt. charge etc. will become payable by the contractor. But the Bank Authority shall deduct Income Tax as per existing rule from contractor's bill. Bill will be paid as per actual measurement not as per schedule.
2.10	ANALYSIS OF RATES	Shall has to be submitted as and when required as per request of the Authority/Bank Authority.
2.11	PRICE ESCALATION	No claim for price escalation shall be entertained up to the completion time.
2.12	TOOLS, MACHINERY AND EQUIPMENT	All tools, equipment and machinery, etc. required for execution of the work are to be arranged by the contractor at his/their own cost. The contractor must also arrange additional tools, equipment if required when asked by the Authority/ Authority.



MODHUMOTI BANK PLC., Khandker Tower (Level-7 & 8), 94 Gulshan Avenue, Gulshan-1, Dhaka-1212

ABSTRACT OF TENDER

- | | | |
|------|---|--|
| 2.13 | MATERIAL STORAGE | Contractor shall be responsible for storage, security of material and equipment as site at his own cost till the completion of the work. |
| 2.14 | POWER, WATER ETC. | The contractor must provide required power and water at his/ their own cost to complete the project. |
| 2.15 | APPROVAL OF MATERIAL & SAMPLE OF WORKS | All materials must be approved [in whiting] by the Bank Authority. |
| 2.16 | QUALIFICATION OF CONTRACTOR | <ul style="list-style-type: none"> i) The Tenderer shall be given priority who has experience of "Construction, Interior decoration and Furniture supply works" in the field of Bank Interiors in Bangladesh, which must be executed by the contractor during last three financial years ii) All experiences must be backed by with proper documentation (i.e. work order, completion certificate) from respective banks. iii) Up to date Trade license, Income Tax clearance certificate, VAT & BIN Certificate. iv) Must be financially solvent. |
| 2.17 | DESIGN AND DRAWINGS | Bank shall produce to the awarded contractor |
| 2.18 | SUBMISSION OF TENDER | Contractor will fill up all the papers containing in the tender Schedules duly signed and sealed and submit it as tender. |
| 2.19 | SUBMISSION OF SAMPLE | The bidder will have to submit samples of important materials/ fittings if needed by the Authority/ Bank Authority as mentioned in schedule of items of works.. |
| 2.20 | EARNEST MONEY | Not Required |



**BOQ FOR CIVIL & INTERIOR DECORATION WORKS OF
MODHUMOTI BANK PLC. JHINAIDA BRANCH**

	PARTICULARS	AMOUNT (BDT)
A	CIVIL WORKS:	
B	TILES & STONE WORKS :	
C	PLUMBING & SANITARY WORKS :	
D	ELECTRICAL & LIGHTING WORKS:	
E	INTERIOR DECORATION WORKS	
F	FURNITURE WORKS:	
G	INTERNET NETWORKING	
	TOTAL (BDT) =	



[Handwritten signature]

**BOQ FOR CIVIL & INTERIOR DECORATION WORKS OF
MODHUMOTI BANK PLC. JHINAIDA BRANCH**

Item No	Description	Unit	Quantity	Rate	Total
1.	CIVIL WORKS:				
1.01	5" BRICK WORK:				
	5" Thickness Brick work (1:4) with 1st class bricks - all complete as per direction of consulting architect & full satisfaction of the Bank authority.	sft.	920		0.0
1.02	VAULT WORK (8'-11"x12'-3"): Wall thickness 8"-10", Roof thickness 4", Floor thickness 3"				
	Reinforced cement concrete works (1:2:4) having minimum crushing strength 18 Mpa (cylinder) at 28 days with cement, best quality coarse sand (50% quantity of best local sand (F.M.-1.5) and 50% quantity of Sylhet sand or coarse sand of equivalent (F.M.-2.5) picked jhama chips including breaking chips and screening, centering, deformed bar 8-12 mm depends on slab size, double layer, c-c 5" spacings shuttering, supplying polythene sheet for making shuttering leak proof, placing of rod in position, mixing the aggregates, casting in forms, compacting & curing for 15 days if possible including the cost of reinforcement and its fabrication as per design drawing and direction of Engineer/Authority.	1	job		0.0
1.03	ROLLING SUTTER:	sft.	44		0.0
1.04	COLLAPSIBLE GATE	sft.	64		0.0
1.05	CEMENT PLASTER	Sft.	1300		0.0
1.06	PLASTIC PAINT	Sft.	3500		0.0
1.07	ENAMEL PAINT	Sft.	320		0.0
1.08	ROLLING SUTTER BOX:	nos	2		0.0
				Sub Total=	0.0
2.	TILES & STONE WORKS :				
2.01	Homogeneous Floor Tile(Mat)				
2.02	(A) size-24"x24"	Sft.	2,000.00		0.0
2.03	(B) size-16"x16"	Sft.	250.00		0.0
2.04	Ceramic Wall Tile (RAK)				
	(A) size-8"x12"	Sft.	470.00		0.0
	(B) size-1'x2'	Sft.	15.00		0.0
				Sub Total=	0.0
3	PLUMBING & SANITARY WORKS :				
3.01	COMBI COMMUNE SET [Victory/Huida/Chinese/RAK]	Nos.	2.00		0.0
3.02	CABINET BASIN/NORMAL BASIN	Nos.	1.00		0.0
3.03	STAINLESS STEEL SINK	Nos.	1.00		0.0
3.04	UPVC [SOIL & WASTE WATER] PIPE [AZIZ]				
a	2" dia pipe	Rft.	30.00		0.0
b	3/4" dia pipe	Rft.	100.00		0.0

Item No	Description	Unit	Quantity	Rate	Total
c	x) Masic pipe (Best Quality)	Nos	3		0.0
d	xii) 4" pvc pipe	Rft.	60		0.0
e	xiii) 4" pvc door trap	Nos	2		0.0
f	xiv) 4" pvc long trap	Nos	2		0.0
g	xv) 4" pvc plane bend	Nos	8		0.0
h	xvii) 1/2" upvc Thrate Pipe	Rft.	40		0.0
i	xviii) 1/2" GI T	nos	9		0.0
j	xix) 1/2" elbo	nos	16		0.0
k	xx) 1/2" GI bon plug	nos	7		0.0
l	xxi) 1/2" GI Scock	nos	10		0.0
m	xxii) 1/2" GI Nipple	nos	10		0.0
n	xxiii) 1/2" - 3/4" Elbo	nos	6		0.0
o	xxiv) 3/4" Upvc Thrate pipe	Rft.	40		0.0
p	xxv) 3/4" GI Socket	nos	6		0.0
q	xxvi) 3/4" Elbo	nos	15		0.0
r	xxvii) 3/4" gate valbe	nos	2		0.0
s	xxviii) 3/4" Union socket	nos	6		0.0
t	xxix) 3/4" Nipple	nos	7		0.0
u	xv) 4" pvc offset	nos	3		0.0
3.05	<u>G.I (Water Supply) pipe (Basundhara Gold)</u>				
a	1/2" Dia Pipe	Rft.	50.00		0.0
3.06	<u>MISCELLANEOUS TOILET FITTINGS</u>				
	[Local / Foreign made]				
3.07	<u>[A] TOWEL RAIL (Meco)</u>	NOS	4.00		0.0
3.08	Best quality available C.P. towel rail of 600 mm x 20 mm size with C.P. holder, screws etc.				
3.09	<u>[B] ANGEL STOP (Nazma Local)</u>	Nos.	3.00		0.0
	Best quality available 12 mm heavy type C.P concealed angle stop cock.				
3.10	<u>[C] 2 in 1 BIB COCK (Nazma Local)</u>	Nos.	2.00		0.0
	Best quality available heavy type 12 mm C.P concealed bib cock.				
3.11	<u>[D] PILLER COCK (Nazma Local)</u>	Nos.	1.00		0.0
	Best quality available heavy type 12 mm C.P pillar cock				
3.12	<u>[E] BIB COCK (Nazma Local)</u>	Nos.	3.00		0.0
	Best quality available heavy type 12 mm C.P Concealed bib cock.				
3.13	<u>[F] SINK COCK (Nazma Local)</u>	Nos.	1.00		0.0
	Best quality available heavy type 12 mm C.P Concealed moving cock.				
3.14	<u>[G] HAND SHOWER (Foreign)</u>	Nos.	2.00		0.0
	Supplying, fitting and fixing best quality local made had shower approved quality complete in all respect as per design, drawing and direction of Engineer/Authority.				
3.14	<u>[H] BOTTLE TRAP (Nazma Local)</u>	Nos.	1.00		0.0
	Best quality available heavy type C.P bottle trap.				
3.15	<u>[I] SOAP TRAY (Local)</u>	Nos.	1.00		0.0
	Best Quality available C.P Soap tray of standard size in/c all fittings etc.				

Item No	Description	Unit	Quantity	Rate	Total
3.16	<u>[J] CONNECTION PIPE [Foreign]</u>	Nos.	3.00		0.0
	Best quality available 12 mm dia plastic connection pipe of required length with brass coupling at both end.				
3.17	<u>[K] PAPER HOLDER [Local]</u>	Nos.	2.00		0.0
	Best Quality available heavy type C.P paper holder in/c one roll of paper.				
3.18	<u>[L] FLOOR GRATING (Local)</u>	Nos.	4.00		0.0
	Best Quality available stainless steel made square type floor grating in traps or in drains.				
3.19	<u>[M] GATE VALVE (ITAP brand, pedrollo)</u>	Nos.	1.00		0.0
	Supplying, fitting & fixing best quality Italian made 'ITAP' brand ½" dia gate valve complete in all respect as per design, drawing and direction of Engineer/Authority.				
3.20	<u>[N] BASIN MIRROR (Foreign)</u>	Nos.	1.00		0.0
	Supplying, fitting & fixing best quality mirror made by float glass on wall fixed by approved type glass holder complete in all respect as per design, drawing and direction of Engineer/Authority.				
3.21	MIRROR SELF	Nos	1.00		0.0
3.22	Magic pipe	Nos	2.00		0.0
				Sub Total=	0.0
4	ELECTRICAL & LIGHTING WORKS:				
4.01	<u>SINGLE TUBE LIGHT</u>	Nos.	4.00		0.0
4.02	<u>LED PANEL LIGHT 8"X 8"</u>	Nos.	70.00		0.0
4.03	<u>LED FLEXIBLE LIGHT</u>	Rft	50.00		0.0
4.04	<u>LED PANEL LIGHT 2'X2'</u>	Nos.	4.00		0.0
4.05	<u>EXHUST FAN [Foreign made]</u>				
A	Size : 8"	Nos.	4.00		0.0
B	16" Wall moving Mira	Nos.	3.00		0.0
4.06	<u>STEEL/PVC BOX</u>	Nos.	35.00		0.0
4.07	<u>PIPE WORKS</u>				
	Supplying, fitting and fixing concealed water grade PVC pipes, complete in all respect as per design drawing and direction of Engineer/Authority.				
	[A] ¾" dia	Rft.	600.00		0.0
	[B] 1" dia	Rft.	300.00		0.0



Item No	Description	Unit	Quantity	Rate	Total
	[C] 1" Flugibole Pipe	Rft.	300.00		0.0
	[D] 3/4" Flugibole Pipe	Rft.	600.00		0.0
4.08	<u>CABLES WORKS [BRB/Paradise/ Approved]</u>				
	1 Coil = 100 yds/91.44 m				
	Supplying and installation of following BYA single core BRB/Paradise/Approved (BRB) Brand cable through prelaidd PVC pipe/channel with all accessories as per design, drawing and direction of Engineer/Authority.				
	[A] 1.5 rm BYA	Coil	15.00		0.0
	[B] 2.5 rm BYA	Coil	15.00		0.0
	[C] 4 rm BYA	Coil	6.00		0.0
	[D] 16 rm cable	Rft	170.00		0.0
	(E) Telephone Cable (2 Pair)	Coil	5.00		0.0
4.09	<u>EARTH CONTINUITY CONDUCTOR [ECC]</u>				
	<u>GREEN COLOUR</u>				
	[A] 1.5 Re BYA ECC	Coil	12.00		0.0
4.10	<u>ELECTRICAL GANG SWITCHES</u>				
	[A] 2-Gang MK Switch	Nos.	5.00		0.0
	[B] 3-Gang MK Switch	Nos.	8.00		0.0
	[C] 4-Gang MK Switch	Nos.	8.00		0.0
	[D] 20 A DP Switch	Nos.	3.00		0.0
	<u>ELECTRICAL SOCKET</u>				
	[A] 3 pin round 15 amp socket	Nos.	5.00		0.0
	[B] 2 pin socket	Nos.	3.00		0.0
	[C] Telephone Socket	Nos.	9.00		0.0
	(D) 13 amp 8 pin socket	Nos.	25.00		0.0
4.11	<u>MCB/MCCB's (Legrand /ENERGYPACK)</u>				
	[A] 10 to 30 amp SP MCB-6KA	Nos.	7.00		0.0
	[B] 20 to 40 amp TP MCB-6 KA	Nos.	15.00		0.0
	(C) 63am TP McB	nos	4.00		0.0
	[D] 50 to 125 amp TP MCCB-25 KA	Nos.	2.00		0.0



Item No	Description	Unit	Quantity	Rate	Total
4.12	DESTRIBUTION BOARD (ENERGYPACK)				
	(A) Sub-Distribution Board	Nos.	2.00		0.0
	(B) Bugler Alarm	Nos.	1.00		0.0
4.13	EARTHING SYSTEM	Job	1.00		0.0
				Sub Total=	0.0
5	INTERIOR DECORATION WORKS				
5.01	TEMPERED GLASS DOOR				
	(A) Size : 3' - 0" w x 7'-0" H	Nos.	2.00		0.0
	(B) Size : 2' - 6" w x 7'-0" H	Nos.	3.00		0.0
5.02	FRAMELESS GLASS PARTITION				
	Supplying, fitting and fixing 10 mm thick clear float glass partition, upper and lower sides are fixed with 3" aluminum armour section, complete in all respect as per design, drawing and direction of Engineer/Authority.	Sft.	130.00		0.0
5.03	GROOVED MINERAL BOARD/GYPSUM BOARD FALSE CEILING				
	A) GYPSUM Board False ceiling (Size 2'x 2') (15mm Thick)	Sft.	1,800.00		0.0
5.04	PLAIN PARTEX FALSE CEILING & PANELING	Sft.	150.00		0.0
5.05	MELAMINE BOARD COLUMN PANELING & FALSE CEILING	Sft.	250.00		0.0
5.06	PARTEX FLUSH DOOR	Nos.	2.00		0.0
5.07	PVC DOOR	Nos.	2.00		0.0
5.08	Door Lock	Nos.	2.00		0.0
5.09	VENETIAN BLIND (VERTICAL)	Sft.	130.00		0.0
	Supplying, fitting & fixing in position imported best quality 125 mm wide vertical blinds of approved colour and quality with all imported accessories complete in all respect as per design, drawing & direction of Engineer/Authority.				
5.10	SELF ADHESIVE FROSTED PAPER	Sft.	130.00		0.0
	Supplying, fitting & fixing frosted paper on Main entry door and other glass surfaces after cutting logo and lettering with fine finish, complete in all respect as per design, drawing & direction of Engineer/Authority.				
5.11	Cash counter	rft	12.00		0.0
5.12	Kitchen Counter	rft	6.00		0.0
5.13	Notice Board	nos	1.00		0.0
5.14	White Board Drop Wall & Partition	Sft.	30.00		0.0
				Sub Total=	0.0



Item No	Description	Unit	Quantity	Rate	Total
6	FURNITURE WORKS:				
	LOW/FULL HIEGHT/HANGING CABINIT (LOCAL)				
	(Rate will be given by measuring surface area)				
6.01	LAMINATED BOARD CABINET	Sft.	174.00		0.0
6.02	KITCHEN CABINET	Rft	6.00		0.0
6.03	MANAGER TABLE WITH SIDE TABLE	Nos.	1.00		0.0
6.04	SECOND MANAGER TABLE WITH SIDE TABLE	Nos	1.00		0.0
6.05	CHEQUE WRITEN TABLE	Nos	1.00		0.0
6.06	OFFICER TABLE	Nos.	4.00		0.0
6.07	DRAWER UNIT	Nos.	9.00		0.0
6.08	ACCOUNT OPENING TABLE	Nos	1.00		0.0
6.09	PHOTO COPY DESK	Nos	1.00		0.0
6.10	MANAGER CHAIR:				
	Supply, fitting & fixing Chair with midium tilted back, foreign fabric and 5 leg with wheel.all complete as per direction and full satisfaction of the Engineer in charge.	nos	1.00		0.0
6.11	MANAGER VISITOR CHAIR:				
6.12	Supply, fitting & fixing Visitor's Chairs with fabric cover tilted back ,without leg.All complete as per direction of the Engineer in charge.	nos	2.00		0.0
6.13	MINI MEETING TABLE 3' ROUND DIAMETER	nos	1		0.0
6.14	OFFICER CHAIR:	nos	10		0.0
6.15	OFFICER VISITOR CHAIR:	nos	12		0.0
6.16	MEETING CHAIR	nos	3		
6.17	DINING TABLE	nos	1		0.0
6.18	DINING CHAIR	nos	3		0.0
6.19	SOFA (Double seated)	nos	3.00		0.0
6.20	COMPLAIN BOX	nos	1.00		0.0
6.21	TEA TABLE	nos	1.00		0.0
				Sub Total=	0.0
7.00	Internet Networking				
7.01	Cable cat-6 (Brand - Systimax/Panduit)	box	2.00		0.0
7.02	Dual Face plate with modular (Brand - Panduit/Systimax original)	nos	11.00		0.0
7.03	Switch: dlink, 24 port, managable	nos	1.00		0.0
7.04	Patch cord(1 metre)	nos	12.00		0.0
7.05	Patch cord(3 metre)	nos	12.00		0.0
7.06	Patch Panel	nos	1.00		0.0
7.07	Cable manager	nos	1.00		0.0
7.08	IT Rack	nos	1.00		0.0
				Sub Total=	0.0



**BOQ FOR CIVIL & INTERIOR DECORATION WORKS OF
MODHUMOTI BANK PLC. JHINAIDA ATM BOOTH**

	PARTICULARS	AMOUNT (BDT)
A	CIVIL WORKS:	
B	ELECTRICAL & LIGHTING WORKS:	
C	INTERIOR DECORATION WORKS	
D	INTERNET NETWORKING	
	TOTAL (BDT) =	



**BOQ FOR CIVIL & INTERIOR DECORATION WORKS OF
MODHUMOTI BANK PLC. JHINAIDA ,ATM BOOTH**

Item No	Description	Unit	Quantity	Rate	Total
1.	CIVIL WORKS:				
1.01	Shutter gate	sft.	50		0.0
1.02	Plastic Paint	sft.	300		0.0
1.03	5" Brick work	L,S	1		0.0
1.04	Tiles (24"x24")				
0.00	Mirror Polished / Homogeneous Floor Tile (Foreign)	sft.	70		0.0
				Sub Total =	0.0
2	ELECTRICAL & LIGHTING WORKS:				
2.01	SINGLE TUBE LIGHT	Nos.	1		0
2.02	ENERGY SAVING DOWN LIGHT	Nos.	2		0
2.03	STEEL/PVC BOX	Nos.	5		0
2.04	PIPE WORKS				
	[A] 1" dia	Rft.	50		0
	[B] 1" Plugibole Pipe	Rft.	25		0
	[C] band, socket, tape etc	job	1		0
2.05	CABLES WORKS [BRB/Paradise/ Approved]				
	1 Coil = 100 yds/91.44 m				
	[A] 1.5 m BYA	Coil	1		0
	[B] 2.5 mm BYA	Coil	1		0
2.06	EARTH CONTINUITY CONDUCTOR [ECC]	job	1		0.00
	GREEN COLOUR				
	[A] 1.5 mm BYA ECC	Coil	1		0.0
2.07	ELECTRICAL GANG SWITCHES				
	[A] 4-Gang MK Switch	Nos.	2		0.0
2.08	<u>ELECTRICAL SOCKET</u>				
	[A] 3 pin flat 13 amp socket	Nos.	2		0.0
	[B] 3 pin round 15 amp socket	Nos.	2		0.0
	[C] 13 amp 8 pin socket	Nos.	4		0.0
2.09	<u>MCB/MCCB's (Legrand /ENERGYPACK)</u>				
	[A] 10 to 30 amp SP MCB-6KA	Nos.	3		0.0
				Sub Total =	0.0



**BOQ FOR CIVIL & INTERIOR DECORATION WORKS OF
MODHUMOTI BANK PLC. JHINAIDA ,ATM BOOTH**

Item No	Description	Unit	Quantity	Rate	Total
3	<u>INTERIOR DECORATION WORKS</u>				
3.01	TEMPERED GLASS DOOR				
	Size : 2'-6" w x 7'-0" H	Nos.	1		0.0
	10MM Glass Partition	Sft	18		0.0
3.02	False ceiling	Sft	70		0.0
3.03	White Board partition+Drop Ceiling	sft	70		0.0
	Hanging shelf / Cabinet	Nos	1		0.0
				Sub Total =	0.0
4	<u>Internet Networking</u>				
4.01	Cable cat-6 (Brand - Systimax/Panduit)	box	0.25		0.0
4.02	Dual Face plate with modular (Brand - Panduit/Systimax original)	nos	4		0.0
4.03	Patch cord (1 metre)	nos	4		0.0
				Sub Total =	0.0
				Grand Total =	0.0



[Handwritten signature]

PROJECT TITLE: FURNITURE LAYOUT PLAN OF JHILDAIDAH BRANCH, MBS PLC.


Mustafizur Rahman Bappy

Furniture Layout Plan

Drawing No.

Page 10 of 10

Option-2



MD. SHAFIU AZAM
MD & CEO
MODHUMOTI BANK PLC.

27/09/2025