

**BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT
ITEMS FOR MODHUMOTI BANK PLC, BANANI
ISLAMIC BANKING BRANCH, DHAKA.**

Sl	Details	Amount (TK)
A	GENARAL ENTRY WORKS	
B	CIVIL WORKS	
C	PAINT WORKS	
D	DOOR & INTERNAL PARTITION WORKS	
E	CEILING WORKS	
F	PLUMBING & SANITARY WORKS	
G	ELECTRICAL WORK	
H	MISCELLANEOUS WORK	
I	FURNITURE WORK	
J	INTERNET & NETWORKING WORKS	
	Grand Total (INCLUDING VAT & TAX)	-

In word :



BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR MODHUMOTI BANK PLC, BANANI ISLAMIC BANKING BRANCH, DHAKA.					
SL	Particulars	Qty.	Unit	Rate	Amount
A. GENARAL ENTRY WORKS					
1	TEMPERED GLASS DOOR (3'-0"x7'-0") (MAIN ENTRY). Supply, fitting & fixing of 10 mm Tempered Glass door shutter with door closer at lower side, handle provision, lower side lock, hinge & other accessories etc. All complete as per design, direction and full satisfaction of consulting consultant.	2.00	Nos.		-
2	ENTRY DESIGN WORK (MAIN ENTRY) Supply, fitting & fixing of main entry design made of 3"x1.5" garjon frameing @ 2'x2' grid line, frame over pasted 12mm thick Gorjon ply with HPL & glass All complete as per design, direction and full satisfaction of consulting consultant.	64.00	Sq.ft		-
3	ROLLING SHUTTER (MAIN ENTRY) Supply, fitting and fixing of steel rolling shutter fabricated with strips of imported G.P. sheet of approved thickness and quality, including manual locking arrangement, surface preparation, cleaning, sanding, putty application, one coat of primer/sealer and two coats of approved-quality enamel paint in approved colour, complete with necessary scaffolding, fittings, accessories, labour and all incidental charges. All complete as per approved design, specification and direction of the Bank Authority.	70.00	Sq.ft		-
4	COLLAPSIBLE GATE (MAIN ENTRY) Supply, fitting and fixing of collapsible gate fabricated with 25 mm × 25 mm × 5 mm MS angle bars and 20 mm × 5 mm MS flat bars, including necessary fabrication, fittings and accessories, surface preparation by cleaning and sanding, putty application, one coat of primer/sealer and two coats of approved-quality enamel paint in approved colour, including necessary scaffolding, labour and all incidental charges. All complete as per approved design, specification and direction of the Bank Authority.	78.00	Sq.ft		-
Sub-total=					-
B. CIVIL WORKS					
1	INTERNAL 5" BRICK WALL 5" brick work with 1st class bricks, cement (fresh/shaha/Crawon/ Scan cement) conforming to BDS232), sand (F.M.1.5), mortor (1:4), making bonds with connected walls, raking out joints, sorting, cleaning and soaking the bricks for at least 24 hours before use, screening & washing the sand, curing completed masonry at least for 7 (seven) days including supply of all necessary materials, at site scaffoldings, water, electricity and also all other charges etc. All complete as per design, direction and full satisfaction of consulting consultant.	450.00	Sq.ft		-



BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR MODHUMOTI BANK PLC, BANANI ISLAMIC BANKING BRANCH, DHAKA.					
SL	Particulars	Qty.	Unit	Rate	Amount
2	INTERNAL BRICK WALL & RCC WALL PLASTER Plaster work of minimum 18mm/16mm thick with cement (fresh/shaha/Crawon/ Scan cement) (conforming to BDS232), sand (F.M. not below 1.2) plaster (1:6) to both inner and outer surfaces of walls, finishing corners and edges, screening and washing sand, preparing the masonry and others surfaces by cleaning and washing, curing completed plaster for at least 10 (ten) days including supply at site of all necessary materials, scaffoldings, water, electricity and also other charges etc. All complete as per design direction and full satisfaction of consulting consultant..	1,200.00	Sq.ft		
3	RCC WORK (For Vault, Lintel) Reinforcement cement concrete works (1:1.5:3) with 72.5 grade deformed bar with minimum, fy = 500 Mpa as per design in concrete in accordance with BSTI standard including cutting, straightening, welding and cleaning rusts, if any, bending & binding in position including supplying of G.I wires (22 BWG) etc. providing spacer blocks, minimum 200mm thick wall thickness having minimum crushing strength 4000 psi (cylinder) at 21 days with cement, best quality coarse sand (25% quantity of the best local sand (F.M.-1.5) and 75% quantity of Sylhet sand or coarse sand of equivalent (F.M.-2.5) 3/4" down grade brick chips and screening, centering, shuttering, supplying Polythene sheet (1 kg covering 6.5 sq. meter) for making shuttering leak proof, All complete as per design, direction and full satisfaction of consulting consultant	200.00	Cft		
4	IMPORTED MIRROR POLISH FLOOR TILES. (Size: 24"x24") Supply, fitting & fixing of Imported mirror polish floor tiles (Size: 24"x24") with minimum 3/4" thick cement mortar (1:2) base and fill in joint with same color cement including cutting and laying the tiles in proper way and finishing with care etc. All complete as per design, direction and full satisfaction of Bank Authority.	300.00	Sq.ft		
5	WALL TILES (12"x24"LOCAL) FOR KITCHEN AND WASH ROOM. [RAK/AKIJ/CBC/ STAR or equivalent] Supply, fitting & fixing of 12"x24" local tiles with minimum 3/4" thick cement mortar(1:2) base and fill in joint with same color cement including chipping, cutting and laying the tiles in proper way and finishing with care etc. All complete as per design, direction and full satisfaction of consulting consultant.	150.00	Sq.ft		
6	Floor TILES (16"x16"LOCAL) FOR KITCHEN AND WASH ROOM. [RAK/AKIJ/CBC/ STAR or equivalent] Supply, fitting & fixing of 16"x16" local tiles with minimum 3/4" thick cement mortar(1:2) base and fill in joint with same color cement including chipping, cutting and laying the tiles in proper way and finishing with care etc. All complete as per design, direction and full satisfaction of consulting consultant.	250.00	Sq.ft		



**BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR MODHUMOTI BANK PLC, BANANI ISLAMIC BANKING
BRANCH, DHAKA.**

SL	Particulars	Qty.	Unit	Rate	Amount
7	KITCHEN COUNTER Supply, fitting & fixing of 18mm Marble/Granite on 2.5" thick RCC slab (1:2:4) with 19 mm thick cement mortar (1:2) including necessary 5" brick wall support, laying, cutting, grinding and polishing the stone, proper pointing etc. All complete as per design direction and full satisfaction of consulting consultant..	4.00	Rft		-
8	CASH COUNTER WITH GLASS TOP SCREEN Supply, making, fitting & fixing of cash counter made of 18 -25 mm thick Gorjon ply, front gutter light provision, top & drop finish with 1200X550mm Granite lower working top with 25mm Melamine / Laminated Board fixing over 18mm gorjon ply, front Lighting provision 10mm sticker pasted glass, with power point provision, paint finished, beveled edge 10mm glass & 40 mm aluminium Chenel etc. All complete as per design, direction and full satisfaction of consulting consultant.	12.00	Rft		-
9	Floor Cleaning Work (Deep Clean)	1.00	Job		-
Sub-total=					-
C.	PAINT WORKS				
1	PLASTIC PAINT (Berger) Painting work with 2 coats of plastic paint of approved colour and quality over a coat of primer seal including cleaning the surface, rubbing by pumice stone, sand papering, synthetic putty and necessary scaffolding for all floors etc. All complete as per design, direction and full satisfaction of consulting consultant.	2,500.00	Sq.ft		-
2	ENAMEL PAINT (Berger) Painting work with 2 coats of enamel paint as per approved colour and quality over a coat of primer seal including cleaning the surface, sand papering, putty and necessary scaffolding for all floors etc. All complete as per design, direction and full satisfaction of consulting consultant.	150.00	Sq.ft		-
Sub-total=					-

Handwritten signature



BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR MODHUMOTI BANK PLC, BANANI ISLAMIC BANKING BRANCH, DHAKA.					
SL	Particulars	Qty.	Unit	Rate	Amount
D.	DOOR & INTERNAL PARTITION WORKS				
1	10 MM FIXED GLASS PARTION WORK WITH ALUMINIUM (40MM) "U" CHANEL Supplying, fitting and fixing of this system of 10mm glass (clear) polished edge on 40mm aluminium "U" section with gasket, ss screws shall have to meet the material strength and properties as specified above and meet the relevant European (EN) and American (ASTM) standards applicable to the mentioned Glazed Partition System. All complete as per design direction and full satisfaction of consulting consultant.	140.00	Sq.ft		-
2	TEMPERED GLASS DOOR (3'-0" X 7'-0") Supply, fitting & fixing of 10 mm Tempered Glass door shutter with door closer (BRAND: Original VVP Thailand) at lower side lock, hinge & other accessories etc. All complete as per design direction and full satisfaction of consulting consultant.	3.00	Nos.		-
3	WALL CLADDING WORK Supplying, fitting & fixing of wall cladding made of 2"x1" garjon process wood frame @2'X2' grid line, Over pasted 12mm Melamine board, and other accessories,etc. Also have provision for Light Guarder. All complete as per design direction and full satisfaction of consulting consultant.	220.00	Sq.ft		-
4	PVC BOARD PANELLING WORK for Bank Branding. (Front desk back, & Others wall) Supply, fitting & fixing wall cladding made of 2"x1" gorjon wooden frame @ 2'x2' grid line, frame over pasted 5mm thick PVC board with Colour full Printed PVC graphics etc. All complete as per design direction and full satisfaction of consulting consultant.	200.00	Sft		-
5	DESIGN PARTITION WITH LIGHT PROVISION (5"Thickness) Supplying, fitting & fixing of partition (5" thick & 8'-0" height) made of Melamine board, gorjan wooden framing decorative sheet edge works, provision for Light Guarder etc. All complete as per design direction and full satisfaction of consulting consultant.	98.00	Sft		-



BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR MODHUMOTI BANK PLC, BANANI ISLAMIC BANKING BRANCH, DHAKA.					
SL	Particulars	Qty.	Unit	Rate	Amount
6	COLUMN CLADDING Supply, fitting & fixing of Column cladding made of 2"x1" MS Box Frame Over pasted approved colour 4mm Aluminium Composite panel (ACP) (Brand: ALCO, Tigar, or Equivalent).and all other necessary hardware materials, etc. All complete as per design, direction and full satisfaction of consulting consultant.	140.00	Sq.ft		-
7	10 MM FRAMELESS BACK PASTED GLASS PANELING Supply, fitting & fixing frameless non tempered back stiker pasted glass paneling/partition made of 10 mm thick clear float glass fixed on top & bottom with silver colour best quality aluminium U section with accessories like sealant, neoprene, other hardware etc. having diamond cut bevelled edge at all exposed edges. All complete as per design, direction and full satisfaction of consulting consultant.	120.00	Sq.ft		-
8	SOLID FLUSH DOOR SHUTTER WITH FRAME FOR WASH AND TOILET DOOR. Supply, fitting and fixing of best quality 37mm thick Gorzon solid flush door, including frame by best quality seasoned Garzon wood 2.5" X 6" section with the supply of best quality hardware, 4" metal hinges, clamps, coal tarring of frame, 03 coat enamel paint/vernish etc. All complete as per design, direction and full satisfaction of consulting consultant.	1.00	Nos.		-
9	SOLID FLUSH DOOR SHUTTER WITH FRAME FOR STORE DOOR. Supply, fitting and fixing of best quality 37mm thick Gorzon solid flush door, including frame by best quality seasoned Garzon wood 2.5" X 6" section with the supply of best quality hardware, 4" metal hinges, clamps, coal tarring of frame, 03 coat enamel paint/vernish etc. All complete as per design, direction and full satisfaction of consulting consultant.	1.00	Nos.		-
10	SOLID FLUSH DOOR SHUTTER WITH VISION PANEL (wash zone) Supply, fitting and fixing of best quality Gorzon solid flush door with vision panel, including frame by best quality seasoned Garzon wood 2.5" X 6" section with the supply of best quality hardware, 4" metal hinges, clamps, coal tarring of frame, 03 coat enamel paint/vernish etc. All complete as per design, direction and full satisfaction of consulting consultant.	1.00	Nos.		-



BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR MODHUMOTI BANK PLC, BANANI ISLAMIC BANKING BRANCH, DHAKA.					
SL	Particulars	Qty.	Unit	Rate	Amount
11	DOOR LOCK Supply, fitting & fixing of hendle type Imported door lock in position of best quality silver colour including all required accessories ensuring minimum injury to door shutter and frame etc. All complete as per design, direction and full satisfaction of consulting consultant.	5.00	Nos.		-
12	DOOR CLOSER (for Woden Door), Supply, fitting & fixing of imported door closer of (King Brand,700 Series, Made By Koria) quality in position including all required accessories, ensuring minimum injury to door shutter and frame etc. All complete as per design, direction and full satisfaction of consulting consultant.	1.00	Nos.		-
Sub-total=					-
E.	CEILING WORKS				
1	PERIPHERAL WOODEN DROP CEILING FOR CURTAIN FITTING Supply, fitting & fixing of design wooden drop ceiling suspended from existing R.C.C. slab of the building at the level of as per direction height on made of 18 mm Veneer best quality Gorjon process wood section and Plastic paint fnish, putty, racking out joints etc. all complete as per design, direction and full satisfaction of the Architect / Engineer / Bank authority.	300.00	Sq.ft		-
2	DECORATIVE WOODEN DROP CEILING Supply, fitting & fixing of design wooden drop ceiling suspended from existing R.C.C. slab of the building at the level of as per direction height on made of 12 mm plain board, 1/2" thick <u>Veneer board</u> over frame work of 2" X 1" best quality Gorjon process wood section and 3 coats of Hand Polish over primer coat, putty, racking out joints etc. all complete as per design, direction and full satisfaction of the Architect / Engineer / Bank authority.	250.00	Sq.ft		-
3	DECORATIVE GYPSUM DROP CEILING Supplying fitting & fixing of Decorative gypsum drop ceiling made of fired rated Gypsum board ceiling with imported (Brand: Elephant or equivalent) 12mm thick gypsum board size : 8'x 4', omega channel frame suspended from roof, best quality hardware etc. All complete as per design direction and full satisfaction of consulting consultant.	1,800.00	Sft		-
Sub-total=					-



BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR MODHUMOTI BANK PLC, BANANI ISLAMIC BANKING BRANCH, DHAKA.					
SL	Particulars	Qty.	Unit	Rate	Amount
F.	PLUMBING & SANITARY WORKS				
1	MIRROR Supply, fitting & fixing of best quality Mirror with wooden frame, necessary hardware. All complete as per design, direction and full satisfaction of consulting consultant.	4.00	No		-
2	COMBI COMODE SET (RAK/ Equivalent) Supplying, fitting and fixing of Supper quality European type glazed combi closet (Floor mount) 725 mm x 360 mm x 840 mm size, including seat cover, Flash Valve system, preparing the base with cement concrete and with wire mesh or rods if necessary, and fitting, fixing, finishing complete with all necessary fittings and connections approved and accepted by the Design Consultant	2.00	No		-
3	Wash Basin for kitchen Supplying, fitting and fixing of under counter type wash basin including screws and mending good the damages with cement mortar (1:4), etc. all complete approved and accepted by the Design Consultant .	4.00	No		-
4	STEEL SINK Supply, fitting & fixing of Stainless Steel sink (size 36" X 18") of (Sweet Home, Thiland) with necessary hardware etc. All complete as per design, direction and full satisfaction of consulting consultant.	1.00	No.		-
5	SANITARY FITTINGS (Brand: Rosa/Haibali or equivalent) Supply, fitting & fixing of toilet fittings of approved quality with necessary hardware etc. All complete as per design, direction and full satisfaction of consulting consultant.				-
a.	Angle stop cock	8.00	Nos.		-
b.	Basin Weast	4.00	Nos.		-
c.	Pillar cock	4.00	Nos.		-
d.	Sink cock	1.00	Nos.		-
e.	CP gratings	3.00	Nos.		-
f.	Towel rail	2.00	Nos		-
g.	Sink waste	1.00	Nos.		-
h.	Connection pipe (Havy type)	6.00	Nos.		-
i.	Music pipe Best quality	5.00	Nos.		-
6	UPVC [SOIL & WASTE WATER] PIPE WORK FOR KITCHEN. Supplying, fitting and fixing required dia UPVC pipe made by National Polymer/ Aziz/RFL including all UPvcfitting and specials like plain bend, tees, elbows, junctions, etc. in/c gasket and cement joints, making holes in walls and floors and mending good the damages etc, connecting up to main road sewerage fit throw inspection pits complete.	1.00	Job		-



BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR MODHUMOTI BANK PLC, BANANI ISLAMIC BANKING BRANCH, DHAKA.					
SL	Particulars	Qty.	Unit	Rate	Amount
7	CPVC [FRESH WATER LINE] FOR KITCHEN. Supplying, fitting and fixing best quality CPVC pipe (Brand:ERA) of required dia including all special fittings, such as bends, elbows, sockets, reducing sockets, tees, unions, jumnuts, etc. in/c cutting grooves where necessary and fitting the same in concealed way with cement mortar, thrade tape,making holes in walls and floors and mending good the damages etc. All complete as per design, direction and full satisfaction of consulting consultant.	1.00	Job		-
Sub-total=					-
G.	ELECTRICAL WORKS				
	PVC PIPE WORK				
	CONCEALED / EXPOSED CONDUIT Supply and laying of following water grade PVC pipe (Aziz/National Polymer/RFL brand) exposed on false ceiling/Tray with galvanized saddle/hanger as per routing shown in the drawing, specification and direction. The rate shall be inclusive the cost of accessories such as bends, tees, sockets, circular boxes, pull wire, groove cutting etc. All complete as per design, direction and full satisfaction of consulting consultant.				
1	3/4" dia PVC Pipe	2,500.00	R.ft		-
	1" dia PVC Pipe	1,000.00	R.ft		-
	3/4" dia flexible Pipe	600.00	R.ft		-
	1" dia flexible Pipe	600.00	R.ft		-
	1/2" dia flexible Pipe	400.00	R.ft		-
	CABLE WORK Supply & installation including termination of PVC insulated or PVC sheathed single core BRB/PARADISE/ PARTEX /SQ/BBS Brand cable including all accessories of the following sizes etc. All complete as per design, direction and full satisfaction of consulting consultant.				
2	1C-1.5 rm BYA Cable	18.00	Coil		-
	1C-1.5 re BYA Cable	8.00	Coil		-
	1C-2.5 rm BYA Cable	16.00	Coil		-
	1C-4.0 rm BYA Cable	8.00	Coil		-
	1C-10.0 rm NYY Cable (Generator to ATS)	200.00	rft		-
	1C-16.0 rm NYY Cable (METER TO MDB/SDB/ATS)	480.00	Rft		-



BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR MODHUMOTI BANK PLC, BANANI ISLAMIC BANKING BRANCH, DHAKA.					
SL	Particulars	Qty.	Unit	Rate	Amount
3	ELECTRICITY DISTRIBUTION BOARD Supply and installation of SDB boxe(s) of 18 SWG sheet metal enclosed hammer painted with hinged front cover with required nuts, bolts etc. having knockout for conduit / cables entry and exit (Bottom/top as required) for 415/240V TP & N/SP&N operations. The box should have solid neutral link. The M.C.C.B.s and M.C.B.s and bus bar 600Amp are to be supplied by the contractor and be so arranged as to keep knobs of the M.C.C.B.s and M.C.B.s projected over the cover. Each box should have one copper earthing block of required numbers of required dia drilled holes for accommodating the terminals of ECC with copper lug (where applicable) including required No.of brass nuts bolts etc. The bus bar rate shall include the cost of best quality insulators etc. All complete as per design, direction and full satisfaction of consulting consultant.				
	MDB Box - Local Made(Size-1050 x750x 110mm)	1.00	Pcs		-
	SDB Box - Local Made(Size-900 x600x 110mm)	1.00	Pcs		-
	100A TP MCCB (ABB)	2.00	Pcs		-
	80A TP MCCB (ABB)	2.00	Pcs		-
	32A TP MCCB (ABB)	8.00	Pcs		-
	20A SP MCB (ABB)	4.00	Pcs		-
	16A SP MCB (ABB)	14.00	Pcs		-
	10A SP MCB (ABB)	8.00	Pcs		-
	6A SP MCB (ABB)	10.00	Pcs		-
4	LIGHT FITTINGS				
i	LED Panel Light (24"x 24") 4000k Supply, fitting & fixing imported LED panel light shade (24"x 24" @ 40 watt) of approved quality made of 0.6-0.8 mm sheet steel, powder coat finish, back side diffuse reflector, central wing micro perforated white painted steel with 02 nos. All complete as per design, direction and full satisfaction of consulting consultant.	20.00	Nos		-
ii	LED Panel Light (8"x 8") 4000k Supply, fitting & fixing imported LED panel light shade (8"x 8" @ 18 watt) of approved quality made of 0.6-0.8 mm sheet steel, powder coat finish, back side diffuse reflector, central wing micro perforated white painted steel with 02 nos. All complete as per design, direction and full satisfaction of consulting consultant.	20.00	Nos		-
iii	LED SPOT LIGHT (5watt) (MOVABLE SINGLE IMPORTED ADOPTER TYPE) Supply, fitting & fixing imported spot light-3/5 watt (china made) including conceal type shade of approved quality with all other imported accessories etc. All complete as per design, direction and full satisfaction of consulting consultant.	20.00	Nos.		-



BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR MODHUMOTI BANK PLC, BANANI ISLAMIC BANKING BRANCH, DHAKA.					
SL	Particulars	Qty.	Unit	Rate	Amount
iv	SINGLE TUBE LIGTH SHADE T-5 Supply, fitting & fixing single T-5 tube light shade with approved quality with 1 no. tube light etc All complete as per design, direction and full satisfaction of consulting consultant.	30.00	Nos.		-
v	SURFACE MOUNTED LIGHT Supplying, fitting and installation of the imported Concealed Down light of 100-125 mm Diameter or equivalent square shaped, 8 to 10 Watt LED with Driver, should be of NVC/Equivalent European Standard/American Standard approved by the Consultant, for the purpose of providing optimum atmospheric artificial light quality of desired size, shape, color and modular length for any location or zone including all kinds of relevant accessories/ lamps (LED Bulb/ Strips/ CFL/ T5) of desired color to meet the standard requirement. All complete as per design, direction and full satisfaction of consulting consultant.	2.00	Nos		-
vi	IMPORTED LINEAR TUBE LIGHT SHADE [48"X4"X2"] Supply, fitting & fixing of ceiling mounted linear tube light shade made with 16 swg MS sheet with powder coated paint finish, hanging with 12mm threaded rod , T5 led tube light (approved sample) with other necessary accessories etc. All complete as per design, direction and full satisfaction of consulting consultant.	6.00	Nos		-
5	BURGLAR ALARM Supply, fitting & fixing of Burglar alarm. All complete as per design, direction and full satisfaction of consulting consultant.	1.00	Nos		-
6	SWITCH/ SWITCH STEEL BOX				
	Supply and installation of Steel box made of 16 SWG galvanized sheet steel. The work must be earthing block & Painting.				
	1 Gang (3"X3"X2") MK Steel Box	6.00	Nos.		-
	2 Gang MK (3"X3"X2") Steel Box	8.00	Nos.		-
	3 Gang MK (3"X3"X2") Steel Box	8.00	Nos.		-
	4 Gang MK (3"X3"X2") Steel Box	6.00	Nos.		-
	Steel Joint Box (5" X 4" X 2")	5.00	Nos.		-
	1 Gang/2gang/ 3gang (3"X3"X2") MK PVC Box	80.00	gang		-
	Supply and installation of following switch and socket of approved quality (Synergy Model, Legrand, Energypac/Schneider Electric)/ MK MODULAR (Singapore) logic Slimline.				
	5A, 2 Gang (1 way) switch	3.00	Pcs		-
	5A, 3 Gang (1 way) switch	5.00	Pcs		-
	5A, 4 Gang (1 way) switch	10.00	Pcs		-
	5A, 5 Gang (1 way) switch	8.00	Pcs		-
7	Bell push	5.00	Pcs		-
8	20A, DP Switch	1.00	Pcs		-
9	Multi Socket (MK Brand)	55.00	Pcs		-



**BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR MODHUMOTI BANK PLC, BANANI ISLAMIC BANKING
BRANCH, DHAKA.**

SL	Particulars	Qty.	Unit	Rate	Amount
	CEILING, WALL AND EXHAUST FAN				
10	WALL MOUNTED MOVING FAN (FOR DINING ROOM & VAULT ROOM) Supply and installation of 220V, 50Hz imported wall moving fan (GFC Brand, Pakistan made) of 16"/18" dia including all standard accessories etc. All complete as per design, direction and full satisfaction of consulting consultant.	2.00	Nos		-
11	EARTHING WORKS Supplying and installation of Req'd. depth 1½" dia G.I. pipe earth electrode by tube well sinking method including supply of 2 SWG HDDB earthing lead from the bottom of earth electrode to the earthing bar of distribution board. Making an earth inspection pit of size 20" x 20" x 18" inside clear. Bottom of pit shall be 3" thick C.C. work and four side wall shall be 5" thick brick wall with ½" plastering and 3" thick R.C.C. cover slab. The top end of the electrode shall be 3" above from the bottom C.C. work. [Depth of bottom of main electrode 130'-0" from G.L. & length of electrode is 120'-0"]. All complete as per design, direction and full satisfaction of consultant.	1.00	Job		-
Sub-total=					-
H.	MISCELLANEOUS WORKS				
1	DESIGN MS PARTITION Supply, fitting & fixing of MS design partition made of 75mmX25mm / 50mmX25mm thick MS box frame with fabric panel & Docu paint finish etc. All complete as per design direction and full satisfaction of consulting consultant.	24.00	sft		-
2	SDB CABINET Supply, fitting & fixing of SDB Cabinet, made with 18mm gorjon board door shutter, including approve colour varnish, etc. All complete as per design, direction and full satisfaction of consulting consultant.	32.00	Sq.ft		-
3	FROSTED PAPER (Brand: TAKI, Taiwan) Supply, fitting & fixing of adhesive frosted paper on clear glass, pasting & cutting with fine finish etc. All complete as per design, direction and full satisfaction of consulting consultant.				
	(a) Thick frosted/Linear strip type/Combination	200.00	Sq.ft		-
4	WALL PAPER [Origin: "China"] Supply, fitting & fixing of 21" wide role wall paper with visible prominent texture to be fixed on plastered wall/column surfaces, fixed with glue without any bubbles, undulation or defects - etc. All complete as per design, direction and full satisfaction of consulting consultant.	100.00	Sq.ft		-
5	ROLLER BLINDS Supply, fitting & fixing of imported best quality roller blinds of approved colour with all imported accessories say pvc coupling cod controlling chain, etc. All complete as per design, direction and full satisfaction of consulting consultant.	600.00	Sq.ft		-



BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR MODHUMOTI BANK PLC, BANANI ISLAMIC BANKING BRANCH, DHAKA.					
SL	Particulars	Qty.	Unit	Rate	Amount
6	VARTICLE NOTICE BOARD (Size: 2.5'X7') Supply, fitting & fixing of notice board made of teak board & fabric and all other necessary accessories. All complete as per design, direction and full satisfaction of consulting consultant.	1.00	Nos.		-
7	CHEQUE WRITING DESK (L 4'XH3.5'XD 16") Supply, fitting & fixing of cheque writing desk made of veneer board (approve color & grain), have provision for light gutter, Best quality necessary hardware materials etc. All complete as per design, direction and full satisfaction of consulting consultant.	1.00	Nos		-
8	CASH BACK WALL DESIGN PANELLING WORK Supply , fitting & fixing of Cash back wall design cladding work made of 2"x1" gorjon Proses wooden frame, 2'x2'Grid line over pasted particle board, have provision for light gutter, paint finish including other hardware etc. All complete as per design, direction and full satisfaction of consulting consultant.	80.00	Sq.ft		-
9	FABRIC PARTITION (40mm) Supplying at site Low height Imported fabric partitions 3'-6" height made of color fabrics and aluminum frame all complete.etc. All complete as per design, direction and full satisfaction of consulting consultant.	75.00	Sq.ft		-
Sub-total=					-
I	FURNITURE WORKS				
1	TABLE FOR BRANCH MANAGER Supplying at site 6.5'x3.3'x2.5' Imported table with drawer-units made of 25mm thick top and 25mm sides all made of Imported Veneer MDF Board (medium density fiber) Laquer polish finish, same veneer edging and computer wire management system. All complete as per design, direction and full satisfaction of consulting consultant.	1.00	Each		-
2	SIDE TABLE FOR BRANCH MANAGER. Supply, fitting & fixing of 4'-0"x1'-4"x2'-6" Imported Manager's Side Table made of Imported Veneer MDF Board (medium density fiber) Laquer polish finish, locks, support rubber mountings and other standard hardware etc. All complete as per design, direction and full satisfaction of consulting consultant.	1.00	Each		-



BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR MODHUMOTI BANK PLC, BANANI ISLAMIC BANKING BRANCH, DHAKA.					
SL	Particulars	Qty.	Unit	Rate	Amount
3	LOW HEIGHT BACK CABINET FOR BRANCH MANAGER'S. Supply, fitting & fixing of (Height 30" & width 16") Manager's low height Back Cabinet made of Imported Veneer MDF Board (medium density fiber) Laquer polish finish locks, support rubber mountings and other standard hardware etc. All complete as per design, direction and full satisfaction of consulting consultant.	15.00	Sq.ft		-
4	COAT HANGER FOR BRANCH MANAGER ROOM Supplying at site coat hanger for manager room made of MDF (medium density fiber) veneer board, best quality SS coat hoque , and other necessary hardware materials, lecquer polish etc. All complete as per design, direction and full satisfaction of consulting consultant.	1.00	Nos		-
5	TABLE FOR OPERATIONS MANAGER Supplying at site 5'-6"x2'-6" table with drawer-units made of 25mm thick top, Mid panel Imported metal leg, powdercoat paint finishing, both-sides laminated particle-boards having lamination-pasting, PVC edging and computer wire management system. All complete as per design, direction and full satisfaction of consulting consultant.	1.00	Each		-
6	MANAGER OPERATIONS SIDE TABLE Supply, fitting & fixing of 3'-0"x2'-6"x16" Asst. Manager's Side Table made of laminated board of approved color and quality, locks, support rubber mountings and other standard hardware etc. All complete as per design, direction and full satisfaction of consulting consultant.	1.00	Each		-
7	CABINET FOR MANAGER OPERATIONS Supply, fitting & fixing of (Height 30" & width 16") Asst. Manager's Back Cabinet made of laminated board of approved color and quality, locks, support rubber mountings and other standard hardware etc. All complete as per design, direction and full satisfaction of consulting consultant.	20.00	Sq.ft		-
8	COAT HANGER FOR ASST. BRANCH MANAGER ROOM Supplying at site coat hanger for manager room made of laminated board of approved color and quality, best quality SS coat hoque , and other necessary hardware materials, etc. All complete as per design, direction and full satisfaction of consulting consultant.	1.00	Nos		-



BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR MODHUMOTI BANK PLC, BANANI ISLAMIC BANKING BRANCH, DHAKA.					
SL	Particulars	Qty.	Unit	Rate	Amount
9	OFFICER TABLE Supplying at site (4'-6" X 2'-6") tables made of Imported metal leg with powdercoad paint finish, 25mm thick laminated board top, and computer cable wire management system. All complete as per design, direction and full satisfaction of consulting consultant.	4.00	Each		-
10	GB & CUSTOMER SERVICE DESK Supply, making, fitting & fixing of GB /Customer service desk(2'-6" width) made of Imported metal leg with powdercoad paint finish, laminated board (25mm thick) edging, Glass panel, lighting provision, and other standard hardware etc. All complete as per design, direction and full satisfaction of consulting consultant.	4.50	Rft		-
11	COMPLAIN BOX Supplying at site complain box made of 25mm thick laminated particle board table top having both-sides laminated pasted, PVC edging and 2 side Transparent provision etc. All complete as per design, direction and full satisfaction of consulting consultant.	1.00	Each		-
12	SIDE UNIT WITH DRAWER Supply, fitting & fixing of side unit with Drawer made of melamine board, lock and stylist flat shape thai handle etc. All complete as per design & directions of the Consultant.	2.00	Nos		-
13	FIXED DRAWER UNITS (LOCAL) Supplying at site (457mm x 406mm x 711mm) drawer units, made of 18mm thick laminated board with pasted PVC edging, having three drawers, one shutter with locking arrangement etc. All complete as per design, direction and full satisfaction of consulting consultant.	2.00	Each		-
14	KITCHEN OVER HEAD CABINET Supply, fitting & fixing of Kitchen cabinet including shutter made of laminated board (18mm thick) of approved color and quality including locks, support rubber mountings and other standard hardwares etc. All complete as per design direction and full satisfaction of consulting consultant.	8.00	sft		-



BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR MODHUMOTI BANK PLC, BANANI ISLAMIC BANKING BRANCH, DHAKA.					
SL	Particulars	Qty.	Unit	Rate	Amount
15	LOW HEIGHT CABINET Supplying, fitting & fixing low height (height 30" & width 16") cabinet made of 25 mm thick melamine board with melamine resin film, best quality hardware materials etc. All complete as per design, direction and full satisfaction of consulting consultant.	60.00	sft		-
16	FULL HEIGHT CABINET Supplying, fitting & fixing full height cabinet made of 25mm thickness melamine board with melamine resin film, best quality hardware materials etc. All complete as per design, direction and full satisfaction of consulting consultant.	64.00	Sq.ft		-
17	DINING TABLE (WALL MOUNTEND) Supplying at site lunch tables made of 25mm thick Laminated board PVC edging, frame structure 1.5x1.5x1.5mm thick SS box pipe, leg stopper etc. All complete as per design, direction and full satisfaction of consulting consultant. Size: 5'-0"X2'-0"	1.00	Each		-
18	TABLE TOP PARTITION (SCREEN 12" HEIGHT / 24"HEIGHT) Supply, fitting & fixing of Table top screen 12"height /24"height made with fabric & matel frame, including necessary hardware & accessories etc. All complete as per design direction and full satisfaction of consulting consultant.	12.00	sft		-
19	SINGLE SEATED SOFA FOR COSTOMER AREA (approved by Bank) Supply, fitting & fixing of single seated sofa with magazine holder made of wooden frame with full upholstery of imported fabric including necessary hardware and imported wooden leg leaquer finish, and side table etc. All complete as per design, direction and full satisfaction of consulting consultant.	3.00	Nos		-



**BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR MODHUMOTI BANK PLC, BANANI ISLAMIC BANKING
BRANCH, DHAKA.**

SL	Particulars	Qty.	Unit	Rate	Amount
20	DOUBLE SEATEDD SOFA FOR COSTOMER AREA (approved by Bank) Supply, fitting & fixing of double seated sofa with magazine holder made of wooden frame with full upholstery of imported fabric including necessary hardware and imported wooden leg leaquer finish, and side table etc. All complete as per design, direction and full satisfaction of consulting consultant.	2.00	Nos		-
21	SOFA CORNER TABLE Supplying at site Imported sofa corner table (size: 2'-0"X2'-0") made of MDF board with veneer pasted; lacquer finished etc. All complete as per design, direction and full satisfaction of consulting consultant.	2.00	Each		-
22	IMPORTED KEYBOARD TRAY Supply, fitting & fixing key board tray. All complete as per design, direction and full satisfaction of consulting consultant.	8.00	Each		-
23	IIMPORTED WRITING PAD Supplying at site imported writing pad made of rubber. All complete as per design, direction and full satisfaction of consulting consultant.	2.00	Nos		-
24	MANAGER CHAIR Supply, fitting & fixing of Imported high back revolving armed chair for Manager with PU upholstery, tilted back, 5 leg wheel, hydraulic system including necessary hardware & accessories etc. All complete as per design direction and full satisfaction of consulting consultant.	1.00	Each		-



BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR MODHUMOTI BANK PLC, BANANI ISLAMIC BANKING BRANCH, DHAKA.					
SL	Particulars	Qty.	Unit	Rate	Amount
25	OPERATIONS MANAGER CHAIR Supply, fitting & fixing of Imported mid back revolving armed chair for Operation Manager with mash fabric upholstery, tilted back, 5 leg wheel, hydraulic system including necessary hardware & accessories etc. All complete as per design, direction and full satisfaction of consulting consultant.	1.00	Each		-
26	IMPORTED OFFICER'S CHAIR Supply, fitting & fixing of Imported mid back revolving armed chair for officer with mash fabric upholstery, tilted back, 5 leg wheel, hydraulic system including necessary hardware & accessories etc. All complete as per design, direction and full satisfaction of consulting consultant.	8.00	Each		-
27	VISITOR'S CHAIR Supply, fitting & fixing of Imported low back fixed type armed chair for fixed officer visitor with mash fabric upholstery including necessary hardware & accessories etc. All complete as per design, direction and full satisfaction of consulting consultant.	6.00	Each		-
28	DINING CHAIR Supply, fitting & fixing of Dinning Chair made of PVC/Plywood with SS/MS Leg. All complete as per design direction and full satisfaction of consulting consultant.	2.00	Each		-
29	GUARD STOOL & PEON STOOL Supply, fitting & fixing of Imported guard stool for guard /messenger with mash fabric upholstery, wheel, hydraulic system including necessary hardware & accessories etc. All complete as per design, direction and full satisfaction of consulting consultant.	2.00	nos		-
Sub-total=					-

[Handwritten signature]



BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR MODHUMOTI BANK PLC, BANANI ISLAMIC BANKING BRANCH, DHAKA.					
SL	Particulars	Qty.	Unit	Rate	Amount
J. Internet & Networking Works					
1	Supply, fitting and fixing of Networking material like switch, cable, rack, moduler, moduler jack, face plate, connector etc. all complete as per required.				
	a) Cable Cat-6 (Brand -Systemix panduit)	3	Box		
	b) Dual Face Plate with modular (Brand -Systemix panduit)	12	Nos		
	c) Switch D-Link, 24 port, Managable	1	Nos		
	d) Patch Coard (1 Meter)	14	Nos		
	e) Patch Coard (2 Meter) 20A Switch	10	Nos		
	f) Patch Panel	1	Nos		
	g) Cable Manager	1	Nos		
	h) IT Rack-12 U	1	Nos		
Sub-total=					-

[All rates must be including tax and applicable VAT]

