

BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR ATM BOOTH, MODHUMOTI BANK PLC, FENI BRANCH, FENI.

SL	Particulars	Qty.	Unit	Rate	Amount
1	LOCAL MIRROR POLISH FLOOR TILES. (Size: 24"X24") Supply, fitting & fixing of Imported mirror polish floor tiles (Size: 24"X24") with minimum 3/4" thick cement mortar (1:2) base and fill in joint with same color cement including cutting and laying the tiles in proper way and finishing with care etc. All complete as per design, direction and full satisfaction of Bank Authority.	145.00	Sq.ft		-
2	PLASTIC PAINT (Berger) Painting work with 2 coats of plastic paint of approved colour and quality over a coat of primer seal including cleaning the surface, rubbing by pumice stone, sand papering, synthetic putty and necessary scaffolding for all floors etc. All complete as per design, direction and full satisfaction of consulting consultant.	150.00	Sq.ft		-
3	ENAMEL PAINT (Berger) Painting work with 2 coats of enamel paint as per approved colour and quality over a coat of primer seal including cleaning the surface, sand papering, putty and necessary scaffolding for all floors etc. All complete as per design, direction and full satisfaction of consulting consultant.	80.00	Sq.ft		-






**BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR ATM
BOOTH, MODHUMOTI BANK PLC, FENI BRANCH, FENI.**

SL	Particulars	Qty.	Unit	Rate	Amount
4	10 MM FIXED GLASS PARTION WORK WITH ALUMINIUM (40MM) "U" CHANEL Supplying, fitting and fixing of this system of 10mm glass (clear) polished edge on 40mm aluminium "U" section with gasket, ss screws shall have to meet the material strength and properties as specified above and meet the relevant European (EN) and American (ASTM) standards applicable to the mentioned Glazed Partition System. All complete as per design direction and full satisfaction of consulting consultant.	68.00	Sq.ft		-
5	TEMPERED GLASS DOOR (3'-0" X 7'-0") Supply, fitting & fixing of 10 mm Tempered Glass door shutter with door closer (BRAND: Original VVP Thailand) at lower side lock, hinge & other accessories etc. All complete as per design direction and full satisfaction of consulting consultant.	2.00	Nos.		-
7	WALL CLADDING WORK Supplying, fitting & fixing of wall cladding made of 2"x1" garjon process wood frame @2'X2' grid line, Over pasted 12mm Melamine board, and other accessories,etc. Also have provision for Light Guarder. All complete as per design direction and full satisfaction of consulting consultant.	48.00	Sq.ft		-

[Handwritten signature]



**BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR ATM
BOOTH, MODHUMOTI BANK PLC, FENI BRANCH, FENI.**

SL	Particulars	Qty.	Unit	Rate	Amount
8	PVC BOARD PANELLING WORK for Bank Branding. (entry left side wall) Supply, fitting & fixing wall cladding made of 2"x1" gorjon wooden frame @ 2'x2' grid line, frame over pasted 5mm thick PVC board with Colour full Printed PVC graphics etc. All complete as per design direction and full satisfaction of consulting consultant.	98.00	Sft		-
9	DRY PARTITION (3"Thickness) Supplying, fitting & fixing of Dry partition (3" thick & 8'-0" height) made of Melamine board, gorjan wooden /MS Chaneel framing decorative sheet edge works. All complete as per design direction and full satisfaction of consulting consultant.	16.00	Sft		-
10	MINERAL BOARD CEILING Supply, fitting and fixing of mineral ceiling made of 3 mm thick mineral board ceiling, over powder-coated T-bar sections and wall-angle sections at edges, arranged in 2'-0" x 2'-0" grid suspended ceiling system using royal plugs, iron angles, screws, hooks, nails and all necessary hardware and accessories. Complete in all respects as per approved design, specification and direction of the Bank Authority.	32.00	Sft		-
11	PVC PIPE WORK				

[Handwritten signature]



BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR ATM BOOTH, MODHUMOTI BANK PLC, FENI BRANCH, FENI.

SL	Particulars	Qty.	Unit	Rate	Amount
	CONCEALED / EXPOSED CONDUIT Supply and laying of following water grade PVC pipe (Aziz/National Polymer/RFL brand) exposed on false ceiling/Tray with galvanized saddle/hanger as per routing shown in the drawing, specification and direction. The rate shall be inclusive the cost of accessories such as bends, tees, sockets, circular boxes, pull wire, groove cutting etc. All complete as per design, direction and full satisfaction of consulting consultant.				
	3/4" dia PVC Pipe	30.00	R.ft		-
	1" dia PVC Pipe	10.00	R.ft		-
	3/4" dia flexible Pipe	50.00	R.ft		-
	1" dia flexible Pipe	10.00	R.ft		-
	1/2" dia flexible Pipe	20.00	R.ft		-
12	CABLE WORK Supply & installation including termination of PVC insulated or PVC sheathed single core BRB/PARADISE/PARTEX /SQ/BBS Brand cable including all accessories of the following sizes etc.				
	1C-1.5 rm BYA Cable	2.00	Coil		-
	1C-1.5 re BYA Cable	1.00	Coil		-
	1C-2.5 rm BYA Cable	1.00	Coil		-
	1C-4.0 rm BYA Cable	1.00	Coil		-
13	SDB Box - Local Made(Size-900 x600x	1.00	Pcs		-
	32A SP MCB (ABB)	3.00	Pcs		-
	20A SP MCB (ABB)	1.00	Pcs		-
	10A SP MCB (ABB)	2.00	Pcs		-






**BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR ATM
BOOTH, MODHUMOTI BANK PLC, FENI BRANCH, FENI.**

SL	Particulars	Qty.	Unit	Rate	Amount
14	EARTHING WORKS Supplying and installation of Reqd. depth 1½" dia G.I. pipe earth electrode by tube well sinking method including supply of 4 SWG HDBC earthing lead from the bottom of earth electrode to the earthing bar of distribution board. Making an earth inspection pit of size 20" x 20" x 18" inside clear. Bottom of pit shall be 3" thick C.C. work and four side wall shall be 5" thick brick wall with ½" plastering and 3" thick R.C.C. cover slab. The top end of the electrode shall be 3" above from the bottom C.C. work. [Depth of bottom of main electrode 130'-0" from G.L. & length of electrode is 120'-0"]. All complete as per design, direction and full satisfaction of consultant.	1.00	Job		-
15	LED Panel Light (8" X 8") 4000k Supply, fitting & fixing imported LED panel light shade (@ 18 watt) of approved quality made of 0.6-0.8 mm sheet steel, powder coat finish, back side diffuse reflector, central wing micro perforated white painted steel with 02 nos. All complete as per design, direction and full satisfaction of consulting consultant.	5.00	Nos		-
16	LED SPOT LIGHT (5watt) (MOVABLE SINGLE IMPORTED ADOPTER TYPE) Supply, fitting & fixing imported spot light-3/5 watt (china made) including conceal type shade of approved quality with all other imported accessories etc. All complete as per design, direction and full satisfaction of consulting consultant.	2.00	Nos.		-



**BOQ FOR SUPPLY & CONSTRUCTION OF FIT-OUT ITEMS FOR ATM
BOOTH, MODHUMOTI BANK PLC, FENI BRANCH, FENI.**

SL	Particulars	Qty.	Unit	Rate	Amount
17	Supply and installation of Steel box made of 16 SWG galvanized sheet steel. The work must be earthing block & Painting.				
	2 Gang MK (3"X3"X2") Steel Box	2.00	Nos.		-
	1 Gang/2gang/ 3gang (3"X3"X2") MK	6.00	gang		-
	Supply and installation of following switch and socket of approved quality (Synergy Model, Legrand, Energypac/Schneider Electric)/ MK MODULAR (Singapore) logic Slimline.				
	5A, 5 Gang (1 way) switch	1.00	Pcs		-
18	20A, DP Switch	1.00	Pcs		-
19	Multi Socket (MK Brand)	10.00	Pcs		-
Total=					-

[All rates must be including tax and applicable VAT]

