Revised BOQ FOR INTERIOR DECORATION WORKS OF MMBPLC BANANI ISLAMIC BANKING BRANCH, BANANI, ROAD -11, DHAKA

A. Civil Works:					
No.	Particulars	Qty.	Unit	Rate (BDT)	Amount (BDT)
1	**5" BRICK WORK:**				
	5" Thickness Brick work (1:4) with 1st class bricks-all complete as per direction of consulting architect & full satisfaction of the Bank authority.	830	Sft.		
2	**PLASTER WORK:**				
	Minimum 12 mm thick cement sand (F.M.not below 1.2) plaster (1:6) with fresh cement (conforming to BDS 232) to wall both inner- and outer surface, finishing the corner and edges in/c washing of sand, cleaning the surface, scaffolding and curing at least for 7 days etc. all complete in all respect as per direction of the engineer-in-charge.	2000	Sft.		
3	**RCC WORK lintel beam:**	10	Cft		
4	**KITCHEN COUNTER:**				
	Kitchen counter(2'-0" width) made of 3" thick RCC slab (1:2:4) including necessary 5" brick wall support, laying, cutting, grinding,Homoginious tiles (2'x2' and 10 mm thick), proper pointing, bottom of RCC slab will be net cement finish etc.	3.5	Rft.		
5	**CASH COUNTER:**				
	Supply, fitting & fixing of Cash Counter made of Gorjon Board Stretchr and Aesthetic Arch, Best Color docu paint with and 31" thick Melamine Board slab with granite cover, working top with stainless steel, necessary welding, bobing, polishing etc.- as per design, direction of Consulting Architect.	12	Rft		
6	**CERAMIC WALL TILES (8"X12"): at Kitchen Room**				
	supplying, fitting & fixing of 8" x 12" Ceramic tiles at bathroom with minimum 3/4" thick cement morter (1:2) base , cutting and laying the tiles in proper way, setting in position keeping horizontal & vertical alignment with care, pointing & polishing etc.	100	Sft		
7	**HOMOGENEUS MIRROR POLISHED TILES (24"X24") at Main Floor**				
	supplying, fitting & fixing of 24" x 24" homogeneus mat tiles with minimum 3/4" thick cement morter (1:2) base and fill in joint with same colour cement including chipping where necessary, cutting and laying the tiles in proper way, setting in position keeping horizontal & vertical alignment with care, pointing & polishing etc.	1400	Sft		
8	**HOMOGENEUS MAT TILES (12"X12") at Vault Room**				
	supplying, fitting & fixing of 12" x 12" homogeneus mat tiles with minimum 3/4" thick cement morter (1:2) base and fill in joint with same colour cement including chipping where necessary, cutting and laying the tiles in proper way, setting in position keeping horizontal & vertical alignment with care, pointing & polishing etc.	100	Sft		

9	**VAULT WORK (10'-6"x8'-9" :** Wall thickness 8"-10", Roof thickness 4", Floor thickness 3"				
	Reinforced cement concrete works (1:2:4) having minimum crushing strength 18 Mpa (cylinder) at 28 days with cement, best quality coarse sand (50% quantity of best local sand (F.M.-1.5) and 50% quantity of Sylhet sand or coarse sand of equivalent (F.M.-2.5) picked jhama chips including breaking chips and screening, centering, deformed bar 8-12 mm depends on slab size, double layer, c-c 5" spacingshuttering, supplying polythene sheet for making shuttering leak proof, placing of rod in position, mixing the aggregates, casting in forms, compacting & curing for 15 days if possible including the cost of reinforcement and its fabrication as per design drawing and direction of Engineer/Authority.	200	cft		
10	**KITCHEN COUNTER & TOILET COUNTER TILES WORK**	20	Sft		
11	**TILES DISMANTLING WORK**	1500	Sft		
		SUB TOTAL (BDT) =			
B. Paint Works :					
No	**Particulars**	**Qty**	**Unit**	**Rate (BDT)**	**Amount (BDT)**
1	**PLASTIC PAINT (BERGER):**				
	Painting Work with Plastic emulsion paint of approved best quality (Berger) in a sealed container, applying to wall in two coats over a coat of brand specified primer including cleaning drying, making free from dirt, removing all chalked & scaled materials, fungus, sand papering the surface and necessary scaffolding, spreading by brush/ roller/spray etc. all complete as per direction of the engineer-in-charge.	1500	Sft		
2	**ENAMEL PAINT (BERGER):**				
	Painting Work with Enamel paint of approved best quality (Berger) in a sealed container, applying two coats over a coat of brand specified primer or sealer elapsing specified time for drying/recoating including cleaning drying, making free from dirt, grease, wax, removing all chalked & scaled materials, fungus, mending good the surface defects, sand papering the surface and necessary scaffolding, spreading by brush/ roller/spray etc. all complete as per direction of the engineer-in-charge.	200	L,S		
3	**Skim coat**	200	Sft		
		SUB TOTAL (BDT) =			**0.00**
C. Doors & Internal partitions:					
No	**Particulars**	**Qty**	**Unit**	**Rate (BDT)**	**Amount (BDT)**
1	**CNC CUTTING WALL PANELING WITH reflected Acrylic: (8'-0" high) at (Main Entrance in site + workstition zone in side passage**				
a	Supply, fitting & fixing of CNC Cutting partition made of best quality Mdf Board ,Ms Lag,Tree Hol,mdf Board Self , section and imported Acrylic,Duco color ,with wire management per design & direction of architect.	95	sft		
b	**Standing Desk** Supply, fitting & fixing of Gorjon/mdf Board Table Top ms round lag Doco Color / hit Print , all complete as per direcion and full satisfaction of the Engineer / Bank authority.	1	Nos		

Madhumati Bank PLC. CSD Head Office, Dhaka

2	**TEMPERED GLASS DOOR:**				
	b. Size : 3'-0" W x 7'-0" H	2	Nos		
	c. Size : 2'-6" W x 7'-0" H	2	Nos		
3	**PARTEX FLASH DOOR:**				
	Supply, fitting & fixing of best quality RFL Plastic door, including frame with the supply of best quality all hardware, clamps, coal tarring of frame including etc. all complete as per direcion and full satisfaction of the Engineer / Bank authority.	3	Nos		
4	**DOOR LOCK:**				
	Supply, fitting & fixing of round cylinder type imported door lock (with 3 keys) in position of best quality silver color including all required accessories ensuring minimum injury to door shutter and frame etc. all complete as per direcion and full satisfaction of the Architect/ Engineer / Bank authority.	3	Nos		
5	**FIXED GLASS PARTITION:**				
	Supply, fitting & fixing aluminum glass partition made of 10mm clear glass with protector bit of approved color and quality with accessories like sealant, neoprene, other hardware etc. All complete as per direcion and full satisfaction of the Architect/ Engineer / Bank authority.	60	Sft		
6	**DOOR Handle 4' :** Supply, fitting & fixing aluminum handle approved color and quality with accessories like, other hardware etc. All complete as per direcion and full satisfaction of the Architect/ Engineer / Bank authority.	4	set		
		SUB TOTAL (BDT) =			
D. Ceiling & Curtain Glass Work:					
No	**Particulars**	**Qty**	**Unit**	**Rate (BDT)**	**Amount (BDT)**
1	**GYPSUM BOARD CEILING: at Kitchen Room**				
	Supplying, fitting and fixing gypsum board ceiling of 12 mm thick board laminated by mechanical hot press with a milk white PVC membrane with Aluminium T-bar frame in natural anodized finish at 600 x 600 mm in grid suspended from ceiling by 12 SWG double ply wire fixed to the ceiling by rowel plug, screws, hooks, nails etc. maintaining straight lines and desired finished level a bottom face with vertical wooden strut as required in/c making holes in slabs, or beams by electric drill machine and mending good the damages, if any, during execution of the work in/c cost of all materials, electricity, accessories, scaffoldings, labour for installation, screws, nails, etc.	100	Sft		
2	**PLAIN CEILING Full Banking Area** : Supplying, fitting and fixing 12mm plain Partex Board ,1"X2" Gorjon Wood,rowel plug, screws, hooks, nails etc.all complete as per drawing, design, direction of the engineer-in-charge & full satisfaction of the Bank authority.	1100	Sft		
3	**Partition and DROP CEILING**				

	Supplying, fitting and fixing of Design drop ceiling made of 12 mm thick Plan Parte board/ 12 mm thick commercial board with best quality and well seasoned Garjan wood frame of section 75 x 38 mm at 600 x 600 mm in grid, fitted and fixed by plugs, nails, screws etc. in/c French polishing 3 coats over a coat of priming & Plastic paint 3 coats over a coat of priming. all complete as per drawing, design, direction of the engineer-in-charge & full satisfaction of the Bank authority.	100	Sft		
4	**Cash Counter Decorative arch Ceiling** Supply, fitting & fixing of Decorative Ceiling Aesthetic arch Design at Cash Counter ,all complete as per drawing, design, direction of the engineer-in-charge & full satisfaction of the Bank authority.	100	Sft		
5	**Round Ceiling Design at banking passage area** Supply, fitting & fixing of Decorative Ceiiling Aesthetic Round ceiling at passage are ,all complete as per drawing, design, direction of the engineer-in-charge & full satisfaction of the Bank authority.	3	nos		
6	**Cash Counter Back wall** Supply, fitting & fixing of Decorative Partition, Logo freming ,all complete as per drawing, design, direction of the engineer-in-charge and full satisfaction of the Bank authority.	104	sft		
7	**COLUMN COVARING BY MELAMINE BOARD** Decorative Colum Covaring and paneling ,melamine Board, 10mm glass Glass pepar Design all complete as per drawing, design, direction of the engineer-in-charge and full satisfaction of the Bank authority.	150	Sft		
8	**COLUMN COVARING BY COLORED GLASS** Decorative Colum Covaring and paneling,10mm Glass, pepar ,color Design all complete as per drawing, design, direction of the engineer-in-charge and full satisfaction of the Bank authority.	50	sft		
9	**PLAIN PARTEX BOARD PENELING & COVARING at GB** Supply, fitting & fixing plain Board ,1"x2" wood,Back Wall Paneling& Covaring all complete as per drawing, design, direction of the engineer-in-charge and full satisfaction of the Bank authority.	50	Sft		
10	**WALL PAPER at GB Back wall** Supply, fitting & fixing wall paper all complete as per drawing, design, direction of the engineer-in-charge and full satisfaction of the Bank authority.	32	Sft		
11	**Arabic Letter CNC CUTTING at GB Back wall Penel** Supply, fitting & fixing Arabic Letter CNC CUTTING all complete as per drawing, design, direction of the engineer-in-charge and full satisfaction of the Bank authority.	2	nos		
12	**SDB CABINET (18mm gorjon/ Melamine board door shutter, Color/varnish finish)**	56	Sft		
				SUB TOTAL=	
E. Plumbing & Sanitation Work:					
No	**Particulars**	**Qty**	**Unit**	**Rate (BDT)**	**Amount (BDT)**
1	**COMMODE WITH LOW DOWN:**				
	Supply, fitting & fixing of RAK Brand commode set (Off White color) with low down with connection pipe other fittings etc. All complete as per direction & full satisfaction of engineer in charge / bank authority.	2	Nos		
2	**BASIN:**				

a	**COUNTER TYPE:**	4	nos		
b	**PEDESTAL TYPE:**	1	nos		
3	**MIRROR:**				
	Supply, fitting & fixing mirror (6 mm) (foreign made) of best quality with necessary hardware, out side wooden frame etc.	20	Sft		
4	**STEEL SINK:**				
	Supply, fitting & fixing of stainless steel sink (36" x 18") of (RAK / Equivalent Brand) with necessary hardware etc. All complete as per direction & full satisfaction of the Bank Authority.	1	Nos		
5	**SANITARY FITTINGS:**				
	Supply, fitting & fixing of toilet fixture of approved quality including fittings, thread tap,hardware with GI pipe & PVC pipe etc. All complete as per direction & full satisfaction of the Arc.				
	i) Sink Cock (Nazma/ Sharif/Sattar Brand)	1	Nos		
	ii) Angel stop cock (Nazma/ Sharif/Sattar Brand)	6	Nos		
	iii) Bib Cock (Nazma/ Sharif/Sattar Brand)	2	Nos		
	iv) Soap Case (Beco/ Meco/Sattar Brand)	4	Nos		
	v) Towel Rail (Sharif/ Sattar Brand)	4	Nos		
	vi) Toilet Paper holder (Sharif/ Sattar/Nazma Brand)	3	Nos		
	vii) Toilet shower (Sharif/Nazma/ Sattar)	2	Nos		
	viii) Piller Cock (Nazma/ Sharif Brand)	5	Nos		
	ix) 2" pvc pipe (National Polymer/RFL)	20	Rft.		
	x) 3/4" pvc pipe (National Polymer/RFL)	10	Rft.		
	xi) 1/2" pvc pipe (National Polymer/RFL)	20	Rft.		
	xiii) Masic pipe (Best Quality)	6	Nos		
	xviii) 1/2" upvc Thrate Pipe	30	Rft.		
	xix) 1/2" GI T	7	Nos		
	xx) 1/2" elbo	5	Nos		
	xxi) 1/2" GI bon plug	5	Nos		
	xxii) 1/2" - 3/4" Elbo	5	Nos		
	xxiii) 3/4" GI Socket	2	Nos		
	xxiv) 3/4" Elbo	2	Nos		
	xxv) 3/4" gate valbe	4	Nos		
	xxvi) 3/4" Union socket	2	Nos		
	xxvii) 3/4" Nipple	3	Nos		
	xxviii) Thrate tape	5	Nos		
	xxix) 3/4" T	3	Nos		
	xxxi) 1.5" Bend	2	Nos		
	xxxiii) upvc T	6	Nos		
		SUB TOTAL (BDT) =			
F. Electrical Work:					
No	**Particulars**	**Qty**	**Unit**	**Rate (BDT)**	**Amount (BDT)**
1	**PVC PIPE WORK:**				
	A. CONCEALED / EXPOSED CONDUIT Supply, fitting & fixing of following water grade PVC pipe exposed on false ceiling / tray with galvanized saddle/hanger as per routing shown in the drawing, specification and direction. The rate shall be inclusive the cost of accessories such as bends, tees. sockets, circular boxes, pull wire groove cutting, GI wire, sattle, scrow etc. All complete as per direction of the engineer-in-charge & full satisfaction of the Bank authority.				
	a) ¾" dia PVC	1200	Rft.		
	b) 1" dia PVC	600	Rft.		
	c) ¾" dia Flexible Pipe	1200	Rft.		

2	**CABLE WORK:**				
	A. Supply and installation including termination of PVC insulated or PVC sheathed single core **BRB/BBS** Brand cable including all accessories, cable socket of the following size etc. All complete as per direction of the engineer-in-charge & full satisfaction of the Bank authority.				
	i) 1 X 1.5rm(1-W) BYA cable	10	Coil		
	ii) 1 X 2.5rm (7-W) BYA cable	12	Coil		
	iii) 1 X 4rm (7-W) BYA cable	6	Coil		
	B. EARTH CONTINUITY CONDUCTOR				
	Supply and installation of PVC insulated cable (single core BRB cable) used as earth continuity conductor along with cables, in pre installed conduit, including connection to various metallic parts of following sizes etc. All complete as per design and direction & full satisfaction of Engineer-in-charge.				
	i) 1C X 1.5 rm BYA (Green)	10	Coil		
3	**EARTHING SYSTEMS :**				
	Supplying & installation 150' to 180' depth more or less completed all necessary Copper Bar, wire, earth electrod, salt, cowdung etc. in all respect testing and commissioning.	1	Nos		
4	**SUB DISTRIBUTION BOARD:**				
	Supply and installation of SDB box (s) of 18 SWG sheet metal enclosed hammer painted with hinged front cover with required nuts, bolts etc. having knockout for conduit / cables entry and exit (bottom / top as required) for 415/240V TP & N/SP&N operations. The box should have solid neutral link. The M.C.C.B.s and M.C.B.s and bas bar 600 Amp are to be supplied by contactor and be so arranged as to keep knobs of the M.C.C.B.s and M.C.B.s projected over the cover. Each box should have one copper earthling block of required numbers of required dia drilled holes for accommodating the terminals of ECC with Copper lug (where applicable) including required numbers of brass nuts bolts etc. The bus bar rate shall include the cost of best quality insulators etc.				
	a. SDB Box	2	Pc.		
	b. 63A TP MCCB (Legrand, Energypac)	4	Pcs		
	c. 32A SP MCB (Legrand, Energypac)	6	Pcs		
	d. 20A TP MCB (Legrand, Energypac)	10	Nos		
	e. 20A SP MCB (Legrand, Energypac)	10	Nos		
	f. 10A SP MCB (Legrand, Energypac)	15	Nos		
	g. 80 to 100 amp TP MCCB-25 KA	2	Nos		
5	**LIGHT FITTINGS:**				
	i) LED. PANEL LIGHT (8"x8")				
	Supply, fitting & fixing locally available LED Panel light 18 watt of approved color & size including conceal type shade with other necessary accessories etc. All complete as per direction of the Consulting Architect & full satisfaction of Engineer.	20	Nos		
	ii) TUBE LIGHT(4'-0"):	3	Nos		
	iii)T5 LIGHT 1'+2'+3'	4	Nos		
	iv)SPOT LIGHT	18	Nos		
	v) FLEXIBLE STRIP LIGHT(1") double light:	50	Mitar		
	vi)LED LIGHT 24"X24" White color 240V 18WATT	6	nos		
6	**SWITCH/ SWITCH STEEL BOX:**				
	A. Supply and installation of steel box made of 16 SWG galvanized				
	i) 1 Gang MK (3" X 3" X 2") Steel Box	6	Nos		
	ii) 2 Gang MK (3" X 3" X 2") Steel Box	10	Nos		
	iii) 3 Gang MK (3" X 3" X 2") Steel Box	10	Nos		
	iv) 4 Gang MK (3" X 3" X 2") Steel Box	2	Nos		

	B. Supply and installation of following switch and soket of approved quality				
	i) 5A, 2 Gang (1 way) switch	6	Pcs		
	ii) 5A, 3 Gang (1 way) switch	8	Pcs		
	iii) 5A, 4 Gang (1 way) switch	10	Pcs		
	iv) 20A Switch (for Sign board)	2	Pcs		
	v) 10A, 2pin socket	5	Pcs		
	vi) 13A, 3pin socket	4	Pcs		
	vii) 15A, 8pin socket	30	Pcs		
7	**WALL FAN:**				
	A. Supply and installation of 220V, 50Hz imported wall moving fan including all accessories etc. all complete up to testing & commissioning as per direction & full satisfaction of Engineer-in-charge .	3	Nos		
8	**CEILING EXHAUST FAN:**				
	Supply and installation of 220V, 50Hz imported exhaust including all accessories etc. all complete up to testing & commissioning as per direction & full satisfaction of Engineer-in-charge .	2	Nos		
9	**SECURITY ALARM:**				
	Supply, fitting and fixing of SECURITY Alarm etc. all complete as per design, direction and full satisfaction of the Architect.	1	Nos		
		SUB TOTAL (BDT) =			
G. Internet & Networking Works					
	Supply, fitting and fixing of Networking material like switch, cable, rack, moduler, moduler jack, face plate, connector etc. all complete as per required.				
	i) Cable Cat -6 (Brand -Systemix panduit)	2	Box		
	ii) Duel Face Plate with modular (Brand -Systemix panduit)	11	Nos		
	iii) Switch D-Link, 24 port, Managable	0	Nos		
	iv) Patch Coard (1 Meter)	11	Nos		
	v) Patch Coard (2 Meter) 20A Switch	11	Nos		
	vi) Patch Panel	1	Nos		
	vii) Cable Manager	1	Nos		
	viii) IT Rack	1	Nos		
		SUB TOTAL (BDT) =			**0.0**
H. Miscellaneous Work:					
No	**Particulars**	**Qty**	**Unit**	**Rate (BDT)**	**Amount (BDT)**
1	**FROSTED PAPER WORK:**				
	Supply, fitting and fixing of adhesive frosted paper (Taki Brand) on clear glass, pasting and cutting with fine finish etc. all complete as per design, direction and full satisfaction of the Architect/Engineer.	60	Sft		
2	**ROLLER BLIND WORK:**				
	Supply, fitting and fixing of imported best quality vertical blinds (5" thick) of approved color with all imported accessories say pvc coupling cod controlling chain, bottom weight plate, bottom chain	450	Sft		
3	**COLLAPSIBLE GATE:**				
	Supply, fitting & fixing collapsible gate made of 25mmX25mmX5mm MS angle bar, 20mmX5mm MS flat bar and necessary accessories etc. complete in all respect as per design,as per direction and full satisfaction of the Architect/Engineer.	90	Sft		
4	**ROLLING SUTTER** at second entrance.	32	Sft		
5	**Plain partex Ceiling** at main entry area	100	Sft		
6	**Planter box**	4	Nos		
7	**Tree Plantation**	3	Nos		

8	**01 Bank Logo :** at main entry Supply, fitting and fixing 3mm ACP Board Letter Cutting at main entry etc. all complete as per design, direction and full satisfaction of the Bank authority.	48	sft		
9	**02 Bank Logo :** at cash counter back wall : Supply, fitting and fixing 3mm acrylic necessary material etc all complete as per drawing, design, direction of the engineer-in-charge & full satisfaction of the Bank authority.	1	nos		
10	**03 Bank Logo :** at gb back wall Supply, fitting and fixing 3mm acrylic necessary material etc all complete as per drawing, design, direction of the engineer-in-charge & full satisfaction of the Bank authority.	1	Nos		
11	**Arabic letter Bismillahir Rahmanir Rahim:** at main entry (4'-0"x10") Supply, fitting and fixing of 3mm acrylic lighting etc, all respect as per design, direction and full satisfaction of the Architect/Engineer.	1	Nos		
12	**Calligraphy design (Surah Al-Ikhlas)** at main entry (4'-0"x2')Supply, fitting and fixing 3mm acrylic laser cutting design necessary material etc, all complete as per drawing, design, direction of the engineer-in-charge & full satisfaction of the Bank authority.	1	Nos		
13	**(Square Kufic Style) Allah, bless this house CNC Cutting** at Cash Counter Back wall) Supply, fitting and fixing 12mm plain board/mdf board cnc cutting design necessary material etc, all complete as per drawing, design, direction of the engineer-in-charge & full satisfaction of the Bank authority.	2	nos		
14	**Kufic Calligraphy :** at Column Supply, fitting and fixing of **Bismillahir Rahmanir Rahim** (inject paper letter cutting) of approved color with all necessary material etc. all complete as per design, direction and full satisfaction of the Architect/Engineer.	4	nos		
15	**Reliance, Gratitude,Patience / Rrabic Picture frame** at Manager room	3	nos		
16	**inkjet paper print** at vault wall Operation manager back wall Supply, fitting & fixing inkjet paper print ,3mm pvc Board,other standard hardware,all complete as per direction and full satisfaction of the Bank Authority.	40	Sft		
17	**Picture frame at waiting area** Supply, fitting & fixing inkjet paper print ,10mm glass, stopper other standard hardware,all complete as per direction and full satisfaction of the Bank Authority.	3	Nos		
18	**BROCHEURE HOLDER**	1	nos		
19	**LADIES & GENTS TOILET SIGNAGE**	2	nos		
20	**ACP Paneling & covaring** at main entry				
21	Supplying, fitting & fixing 3mm acp Board ,18 gauge1"x1" ms box , of approved Color and best fininshed,asper design all complete as per direction and full satisfaction of the Engineer in charge.	80	sft		
		SUB TOTAL (BDT) =			
I. Furniture Works:					
No	**Particulars**	**Qty**	**Unit**	**Rate (BDT)**	**Amount (BDT)**
1	**MANAGER TABLE:**				

	Supply, fitting & fixing Manager Table made of Maximum density fibre (MDF) board with licker polish/ Burmateak Veneered Board with french polish, top of polish one coat of white licker will be used, secretariate drawer unit, key board tray , wire cap,leg stopper, SS knob, lock etc.	1	Nos		
2	**MANAGER SIDE TABLE:**				
	Supply, fitting & fixing Manager Table made of Maximum density fibre (MDF) board with licker polish/ Burmateak Veneered Board with french polish, top of polish one coat of white licker will be used, two shelve, shutter, SS knob, Lock, key board tray, leg stopper, wire cap.	1	Nos		
3	**MANAGER BACK CABINET:**				
	Supply, fitting & fixing decorative full height cabinet with Glass shutter, Inside Light made of HPL & Laquuer red oak veniered board, edging (1mm thick), shutter, back side 6mm thick PVC board, conceiled hinge, SS knob, lock, leg stopper other standard hardware,all complete as per direction and full satisfaction of the Bank Authority.	25	Sft		
4	**MANAGER OPERATION TABLE:**				
	Supply, fitting & fixing Asst. Manager Table made of Melamine board, Melamine edging (2mm thick), secretariate drawer unit, key board tray, wire cap, SS knob, lock, concealed hinge,leg stopper, best quality hardware etc, as per direction and full satisfaction of the Bank Authority.	1	Nos		
5	**MANAGER OPERATION SIDE TABLE:**				
	Supply, fitting & fixing Asst. Manager side Table made of Melamine board, Melamine edging(2mm thick), secretariate drawer unit, key board tray, wire cap, SS knob, lock, concealed hinge, best quality hardware etc, as per direction and full satisfaction of the Bank Authority.	1	Nos		
6	**MANAGER OPERATION BACK CABINET:**				
	Supply, fitting & fixing cabinet made of 18mm Melamine board, Melamine edging (1mm thick),back side 6mm thick PVC board, two shelve, shutter, conceiled hinge, SS knob, lock, leg stopper other standard hardware,all complete as per direction and full satisfaction of the Bank Authority.	60	sft		
7	**PHOTOCOPY DESK:**				
	Supply, fitting & fixing photocopy deskmade of 25 mm thick Melamine board, 2mm thick Melamine edging,back side 6mm thick PVC board, leg stopper, drawer, chanel, SS knob, best quality hardware etc .all complete as per direction and full satisfaction of the Bank Authority.	1	Nos		
8	**MOBILE DRAWER:**				
	Supply, fitting & fixing Mobile Drawer made of 18 mm thick Melamine board, 1mm thick Melamine edging, drawer channel, SS knob, lock, best quality hardware etc, .all complete as per direction and full satisfaction of the Bank Authority. (Star Particle Board, Partex Brand).	9	Nos		
9	**FULL/LOW HEIGHT CABINET at manager operation +gb +cash:**				
	Supply, fitting & fixing low height cabinet made of Melamine board, Melamine edging (2mm thick) , leg stopper, SS knob, lock, concealed hinge other standard hardware .all complete as per direction and full satisfaction of the Bank Authority.	92	Sft		

Madhumoti Bank P.L.C. CSD Head Office, Dhaka

10	**KITCHEN CABINET:**				
	Supply, fitting & fixing Kitchen cabinet made of 18 mm thick Melamine board, SS knob, conciled hinge, Shutter, 2mm thick Melamine edging, shelve, best quality hardware, etc.all complete as per direction and full satisfaction of the Bank Authority.	4	rft		
11	**CHEQUE WRITING DESK:**				
	Supply, fitting & fixing Check writing desk made of imported laminated board, 8 mm thick glass, other standard hardware .all complete as per direction and full satisfaction of the Engineer in charge.	1	Nos		
12	**NOTICE BOARD :**				
	Supply, fitting & fixing Notice Board as per bank standard.	1	Nos		
13	**GB/TABLE:**				
	Supply, fitting & fixing Officer Table made of Melamine board, Melamine edging(2mm thick) secretariate wire cap, concealed hinge, best quality hardware etc, as per direction and full satisfaction of the Bank Authority.	3	Nos		
14	**Foreign Trade& Investment Table set with Workstation Partition**	3	Nos		
	Supply, fitting & fixing Officer Table made of Melamine board, Melamine edging (2mm thick) secretariate wire cap, concealed hinge, best quality hardware etc, as per direction and full satisfaction of the Bank Authority.				
16	**MANAGER CHAIR:**				
	Supply, fitting & fixing Chair with midium tilted back, foreign fabric and 5 leg with wheel.all complete as per direction and full satisfaction of the Engineer in charge.	1	Nos		
17	**MANAGER VISITOR CHAIR:**				
	Supply, fitting & fixing Visitor's Chairs with fabric cover tilted back ,without leg.All complete as per direction of the Engineer in charge.	2	Nos		
18	**MANAGER OPERATION CHAIR** =1 +,Cash=3 ,Gb=3,+Foreign Trade& Investment =3:				
	Supply, fitting & fixing Chair with midium tilted back, foreign fabric and 5 leg with wheel.all complete as per direction and full satisfaction of the Engineer.	10	Nos		
19	**OPERATION MANAGER VISITOR CHAIR=2,+ Gb=3:**				
	Supply, fitting & fixing Visitor's Chairs with fabric cover tilted back ,without leg. All complete as per direction of the Engineer in charge.	5	Nos		
24	**DINING CHAIR:**				
	Supply, fitting & fixing Chairs with fabric cover tilted back, without leg. All complete as per direction of the Engineer in charge.	4	Nos		
25	**DINING TABLE:**				
	Supply, fitting & fixing DINING Table made of laminated particle board, both side lamination pasted, pvc edging. all complete as per direction and full satisfaction of the Engineer in charge.	8	rft		
26	**SOFA 2 SEATER:**				
	Sofa (double seated): Supply of sofa made of wooden body with imported foreign rexine (Indonasia) upholstered of approved color 06 legs will be 3"x3" x3" SS box which 2 mm thick.	3	Set		
			SUB TOTAL (BDT) =		