BOQ for Interior decoration "Partition, Washroom, Electrical, Lighting & Cabling, Networking and Miscellaneous" works at **Level-8 (SMT Portion)** of Head Office, Modhumoti Bank PLC.

A. Civil Work

SL	Particulars	Qty.	Unit	Rate (including VAT & AIT)	Total amount
1	**Dismantling works**				
	i) Dismantle of Existing wash room without damaging the building structure & wall	1	Job.		
	ii) Dismantle of existing board partition in a way that adjacent false ceiling & partition would not collapse.	460	sft		
	iii) Dismantle of Existing Plain Board False Celling in a way that adjacent false ceiling & partition would not collapse.	750	sft		
	iv) Dismantle of Existing Gypsum Board False Celling at kitchen, room-2 back side room.	320	sft		
	v) Dismantling of Tiles work (wooden+mirror)	1	Job.		
	vi) Common washroom wall tiles dismantling	1	Job.		
2	**Site Cleaning work**				
	site cleaning by removing all existing devrish from 8th floor to ground floor by manual labour using staircase,then carry those debrish by dump truck to dumping point.	1	Job.		
3	**Tiles work**				
	i) Mirror polished tiles same as existing floor (at room-2 and Dismantle washroom area)	260	sft		
	ii) Malaysian Wall Tiles at common washroom (size: 1'-0"x2'-0")	205	sft		
4	**Brick wall**	180	sft		
5	**Plaster work**	250	sft		
6	**Materials Lifting works**	1	Job.		
				Sub Total Tk =	-

B. Paint Work

SL	Particulars	Qty.	Unit	Rate (including VAT & AIT)	Total amount
1	**PLASTIC PAINT of Wall & Celling (Brand- Berger/ Elite)** Painting work with 2 coats of plastic paint of aprroved colour and quality over a coat of primer seal including cleaning the surface, rubbing by pumice stone, sand papering, synthetic putty and necessary scaffolding for all floors etc. all complete as per design, direction and full satisfaction of the Architect / Engineer/Bank authority.	2,000	Sq.ft		
				Sub Total Tk =	-

C. Door & Internal Partition Work

SL	Particulars	Qty.	Unit	Rate (including VAT & AIT)	Total amount
1	**10 mm Temper Glass Door Re-Installment with NEW Door closer & Fittings**	3	Nos		
2	**Flush Door for Common Toilet**	1	Nos		
3	**Door Lock**	1	Nos		



BOQ for Interior decoration "Partition, Washroom, Electrical, Lighting & Cabling, Networking and Miscellaneous" works at **Level-8 (SMT Portion)** of Head Office, Modhumoti Bank PLC.

4	**Particle Board Partition** Supplying fitting & fixing of 3" thick particle board partition made of garjan wooden frame (2"x1.5" section) with 3" screw on floor & Ceiling and both side ½" thick plain particle board (Star particle/Partex) fittings with nail @ 24" c/c vertical members and at least 2'c/c horizontal. All board surfaces must be level with each other and on the same plane.	410	Sq.ft		
				Sub Total Tk =	-

D. Ceiling Work

SL	Particulars	Qty.	Unit	Rate (including VAT & AIT)	Total amount
1	**2'x2' GRID GYPSUM BOARD CEILING**	510	Sq.ft		
2	**Partex Board Plain & decorative false ceiling**	700	sft		
				Sub Total Tk =	-

E. Electrical Work

SL	Particulars	Qty.	Unit	Rate (including VAT & AIT)	Total amount
	PVC PIPE WORK				
1	**A. CONCEALED / EXPOSED CONDUIT** Supply and laying of following water grade PVC pipe exposed on false ceiling/Tray with galvanized saddle/hanger as per routing shown in the drawing, specification and direction. The rate shall be inclusive the cost of accessories such as bends, tees, sockets, circular boxes, pull wire, groove cutting etc. all complete as per design and direction and full satisfaction of Engineer in charge.				
	1" dia PVC Pipe	200	R.ft		
	3/4" dia flexible Pipe	200	R.ft		
2	**CABLE WORK**				
	A. Supply & installation including termination of PVC insulated or PVC sheathed **single core BRB cable** including all accessories of the following sizes etc. all complete as per design and direction and full satisfaction of Engineer in charge.				
	1C X 1.5 rm BYA cable	6	Coil		
	1C X 2.5 rm BYA cable	5	Coil		
	1C X 1.5 re BYA cable	4	Coil		
3	**LIGHT FITTINGS (size: 8"x8")**				
	PL LIGHT shade Supply, fitting & fixing imported 18W energy saving down light incldluing conceal type shade of approved quality with all other imported accessories etc. all complete as per direction and full satisfaction of Engineer in charge. (Energypac/ Super Star)	20	Nos.		
4	**2'x2' LED Panel Light (48w)**	10	nos		
5	**Spot light**	10	nos		
5	**SWITCHE & SOCKET :**				
a	**Supply & Installation 3 Gang Switches** 10Amp with imported Brand. (Legrend/super star brand)	4	pcs		
b	Supply & Installation16Amp **2-Pin Switch Socket** outlet. **(MK/super star brand)**	4	Nos		
c	Supply & Installation **6Pin Multi socket -super star**	6	Nos		

BOQ for Interior decoration "Partition, Washroom, Electrical, Lighting & Cabling, Networking and Miscellaneous" works at **Level-8 (SMT Portion)** of Head Office, Modhumoti Bank PLC.

6	**Dismantalling Works All Electric Item**	1	Job		
				Sub Total Tk =	-

F. Furniture Works

SL	Particulars	Qty.	Unit	Rate (including VAT & AIT)	Total amount
1	**Full/Low Height Cabinet:(Imported quality)** Supply, fitting & fixing of (Height30" & width 16") low height Back Cabinet with best quality 18mm HPL board, locks, support rubber mountings and other standard hardware at factory finish etc. All complete as per design, direction and full satisfaction of consulting consultant.	140.00	Sft		
				Sub Total Tk =	-

G. Missalanious Works

SL	Particulars	Qty.	Unit	Rate (including VAT & AIT)	Total amount
1	**WALL PAPER** [Origin: "China"] Supply, fitting & fixing of 21" wide role wall paper with visible prominent texture to be fixed on plastered wall/column surfaces, fixed with glue without any bubbles, undulation or defects - etc. All complete as per design, direction and full satisfaction of consulting consultant.	900	Sft		
2	**FROSTED PAPER** (Brand: TAKI, Taiwan) Supply, fitting & fixing of adhesive frosted paper on clear glass, pasting & cutting with fine finish etc. All complete as per design, direction and full satisfaction of consulting consultant.	78	Sft		
3	**Wall Bit** made by SS/Cpper or as per recpmmendation by the Bank	100	Rft		
4	**Plumbing Works for common Toilet:** Sypply and fittings of all hardware for 1 commode, 1 basin.	1	Job.		
5	**Roller Blinds:** (at room- 3, 4, 5) Supplying, fitting & fixing in position imported rollar blinds of approved colour and quality with all imported accessories complete in all respect as per design, drawing & direction of Engineer/Authority.	470	Sft		
6	Painting with Frame	6	nos		
				Sub Total Tk =	-

H. Plumbing & Sanitary Works

	Supply, fitting and fixing of Plumbing and sanitary fixtures with all hardware etc. imported or the best quality all complete as per required.				
1	Mirror	1	Nos		
2	Angle Stop Cock	3	Nos		
3	CP gratings	1	Nos		
4	Towel Rail	1	Nos		
5	Connection Pipe (Havy type)	2	Nos		
6	Magic Pipe	1	Nos		
7	Toilet paper Holder	1	Nos		
8	Soap Case	1	Nos		
9	Push Shower	1	Nos		
10	UPVC (Soil & Waste water) Pipe work for Toilet	1	Job		
11	CPVC (Water Line) Pipe work for Toilet	1	Job		

	BOQ for Interior decoration "Partition, Washroom, Electrical, Lighting & Cabling, Networking and Miscellaneous" works at **Level-8 (SMT Portion)** of Head Office, Modhumoti Bank PLC.				
12	**Plumbing Works with laber cost for Common Toilet:** Supply, fitting and fixing of Plumbing and sanitary necessary hardware etc. all complete as per required.	1	Job.		
				Sub Total Tk =	-
I. Internet & Networking Works					
	Supply, fitting and fixing of Networking material like switch, cable, rack, moduler, moduler jack, face plate, connector etc. all complete as per required.				
1	*a) Cable Cat-6 (Brand -Systemix panduit)*	1.50	Box		
	b) Dual Face Plate with modular (Brand -Systemix panduit)	6	Nos		
	c) Patch Coard (1 Meter)	6	Nos		
	d) Patch Coard (2 Meter)	6	Nos		
				Sub Total Tk =	-
				Grand Total Tk. Including VAT & TAX.	-