Ref: No: Ref: No: MMBPLC/HO/CSD/RFQ/2026/11/146/Rev

Date: 11.11.2026

BOQ (Rev) for Interior decoration "Partition, Washroom, Electrical, Lighting & Cabling, and Miscellaneous" Works at **Level-8 of Head Office, Modhumoti Bank PLC.**

Sl	Details	Amount (TK)
A	Civil Works	-
B	Paint works	-
C	Door & Internal Partition Works	-
D	Ceiling Works	-
E	Electrical Works	-
F	Furniture works	-
G	Miscellaneous Works	-
H	Internet & Networking Works	-
	Total Amount (Tk.)=	**-**

In Word: Twelve lac Ten thousand two hundred forty taka only.

BOQ for Interior decoration "Partition, Washroom, Electrical, Lighting & Cabling, and Miscellaneous" works at **Level-8 of Head Office, Modhumoti Bank PLC.**

A. Civil Work

SL	Particulars	Qty.	Unit	Rate (including VAT & AIT)	Total amount
1	**Dismantling works**				
	i) Dismantle of Existing wash room (at room-4 & Common toiltet 1 wall) without damaging the building structure & wall	1	Job.		-
	ii) Dismantle of existing board partition in a way that adjacent false ceiling & partition would not collapse.	400	sft		-
	iii) Dismantle of Existing Plain Board False Celling in a way that adjacent false ceiling & partition would not collapse.	380	sft		-
	iv) Dismantle of Existing Gypsum Board False Celling at kitchen, room-2 back side room.	300	sft		-
	v) Common washroom wall & floor tiles dismantling	1	Job.		-
2	**Site Cleaning work**				
	site cleaning by removing all existing devrish from 8th floor to ground floor by manual labour using staircase,then carry those debrish by dump truck to dumping point.	1	Job.		-
3	**Tiles work:**				
	i) Mirror polished tiles same as existing floor (size: 24"x24") (at room-4 Dismantle washroom area)	20	sft		-
	ii) Matt floor Tiles at common washroom (size: 1'-0"x1'-0", Local)	10	sft		-
	iii) Wall Tiles at common washroom (size: 1'-0"x2'-0", Local)	30	sft		-
4	**Brick wall**	10	sft		-
5	**Plaster work**	0	sft		-
6	**Materials Lifting works**	1	Job.		-
		Sub Total Tk =			-

B. Paint Work

SL	Particulars	Qty.	Unit	Rate (including VAT & AIT)	Total amount
1	**PLASTIC PAINT of Wall & Celling (Brand- Berger/ Elite)** Painting work with 2 coats of plastic paint of aprroved colour and quality over a coat of primer seal including cleaning the surface, rubbing by pumice stone, sand papering, synthetic putty and necessary scaffolding for all floors etc. all complete as per design, direction and full satisfaction of the Architect / Engineer/Bank authority.	1,000	Sq.ft		-
		Sub Total Tk =			-

C. Door & Internal Partition Work

SL	Particulars	Qty.	Unit	Rate (including VAT & AIT)	Total amount
1	**10mm Temper Glass Door Re-Installment & Fittings**	3	Sq.ft		-
2	**Flush Door refitting for Common Toilet**	1	Nos		-
3	**Door Lock**	1	Nos		-
4	**Particle Board Partition** Supplying fitting & fixing of 3" thick particle board partition made of garjan wooden frame (2"x1.5" section) with 3" screw on floor & Ceiling and both side ½" thick plain particle board (Star particle/Partex) fittings with nail @ 24" c/c vertical members and at least 2'c/c horizontal. All board surfaces must be level with each other and on the same plane.	370	Sq.ft		-
		Sub Total Tk =			-

BOQ for Interior decoration "Partition, Washroom, Electrical, Lighting & Cabling, and Miscellaneous" works at **Level-8 of Head Office, Modhumoti Bank PLC.**

D. Ceiling Work

SL	Particulars	Qty.	Unit	Rate (including VAT & AIT)	Total amount
1	**2'x2' GRID MINAREL BOARD CEILING** (at room-2 back side room & common toilet)	200	Sq.ft		-
2	**2'x2' GRID MINAREL BOARD CEILING** (at Dinning room Only Board)	80	Sq.ft		-
3	**Partex Board Plain & decorative false ceiling**	300	sft		-
		Sub Total Tk =			-

E. Electrical Work

SL	Particulars	Qty.	Unit	Rate (including VAT & AIT)	Total amount
1	**PVC PIPE WORK**				
	A. CONCEALED / EXPOSED CONDUIT Supply and laying of following water grade PVC pipe exposed on false ceiling/Tray with galvanized saddle/hanger as per routing shown in the drawing, specification and direction. The rate shall be inclusive the cost of accessories such as bends, tees, sockets, circular boxes, pull wire, groove cutting etc. all complete as per design and direction and full satisfaction of Engineer in charge.				
	1" dia PVC Pipe	200	R.ft		-
	3/4" dia flexible Pipe	200	R.ft		-
2	**CABLE WORK**				
	A. Supply & installation including termination of PVC insulated or PVC sheathed **single core BRB cable** including all accessories of the following sizes etc. all complete as per design and direction and full satisfaction of Engineer in charge.				
	1C X 1.5 rm BYA cable	3	Coil		-
	1C X 2.5 rm BYA cable	3	Coil		-
	1C X 1.5 re BYA cable	2	Coil		-
3	**2'x2' LED Panel Light (48w)**	8	nos		-
4	**SWITCHE & SOCKET :**				
5.	**Supply & Installation 3 Gang Switches** 10Amp with imported Brand. (Legrend/super star brand)	4	pcs		-
6.	Supply & Installation16Amp **2-Pin Switch Socket** outlet. **(MK/super star brand)**	4	Nos		-
7	Supply & Installation **6Pin Multi socket -super star**	6	Nos		-
8	**Dismantalling Works All Electric Item**	1	Job		-
		Sub Total Tk =			-

F. Furniture Works

SL	Particulars	Qty.	Unit	Rate (including VAT & AIT)	Total amount
1	**Low Height Cabinet:(Imported quality)** Supply, fitting & fixing of (Height30" & width 16") low height Back Cabinet with best quality 18mm Melamine board, locks, support rubber mountings and other standard hardware at factory finish etc. All complete as per design, direction and full satisfaction of consulting consultant.	20	Sft		-
		Sub Total Tk =			-

BOQ for Interior decoration "Partition, Washroom, Electrical, Lighting & Cabling, and Miscellaneous" works at **Level-8 of Head Office, Modhumoti Bank PLC.**

G. Miscellaneous Works

SL	Particulars	Qty.	Unit	Rate (including VAT & AIT)	Total amount
1	**WALL PAPER** [Origin: "China"] Supply, fitting & fixing of 21" wide role wall paper with visible prominent texture to be fixed on plastered wall/column surfaces, fixed with glue without any bubbles, undulation or defects - etc. All complete as per design, direction and full satisfaction of consulting consultant.	100	Sft		-
2	**FROSTED PAPER** (Brand: TAKI, Taiwan) Supply, fitting & fixing of adhesive frosted paper on clear glass, pasting & cutting with fine finish etc. All complete as per design, direction and full satisfaction of consulting consultant.	84	Sft		-
3	**Wall T-Bit**	100	Rft		-
4	**Roller Blinds:** (at room- 4, 5) Supplying, fitting & fixing in position imported rollar blinds of approved colour and quality with all imported accessories complete in all respect as per design, drawing & direction of Engineer/Authority.	80	Sft		-
		Sub Total Tk =			-

H. Internet & Networking Works

1	Supply, fitting and fixing of Networking material like switch, cable, rack, moduler, moduler jack, face plate, connector etc. all complete as per required.				
	a) Cable Cat-6 (Brand -Systemix panduit)	1.50	Box		-
	b) Dual Face Plate with modular (Brand -Systemix panduit)	5	Nos		-
	c) Patch Coard (1 Meter)	5	Nos		-
	d) Patch Coard (2 Meter)	5	Nos		-
		Sub Total Tk =			-
Grand Total Tk. =					